



- NOTES:
1. ANY DISTURBED LANDSCAPING WITHIN THE PLANTER BOX AREAS SHALL BE REPLACED IN KIND. THIS WORK SHALL BE PAID FOR AS LANDSCAPING (SPECIAL).
  2. ALL 8-INCH P.C.C. SIDEWALK SHALL BE HIGH EARLY STRENGTH P.C.C.
  3. FOR ADA CURB RAMP DETAILS, SEE SHEETS 125-128.
  4. LONGITUDINAL CONSTRUCTION JOINT. DRILL AND GROUT NO. 8 DEFORMED EPOXY TIE BARS 30" LONG AT 24" C-C SHALL BE INCLUDED IN THE COST OF THE PCC SHOULDER.

**LEGEND**

- PAVEMENT REMOVAL
- AGGREGATE SUBGRADE IMPROVEMENT, 12"
- PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)
- SIDEWALK REMOVAL
- PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH (HIGH EARLY STRENGTH) DETECTABLE WARNINGS
- SIDEWALK REMOVAL
- PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH
- TOPSOIL FURNISH AND PLACE, 4" LANDSCAPING, SPECIAL
- COMBINATION CURB AND GUTTER REMOVAL
- COMBINATION CONCRETE CURB AND GUTTER, TYPE B-V.12
- CONCRETE BARRIER REMOVAL
- CONCRETE BARRIER TRANSITION
- BARRIER BASE
- MODIFY CONCRETE BARRIER AND RETAINING WALL (REMOVAL AND REPLACEMENT)
- PAVED SHOULDER REMOVAL (DAN RYAN) SEE NOTE 4
- PORTLAND CEMENT CONCRETE SHOULDERS, 14" STABILIZED SUB BASE 6" SUB BASE GRANULAR MATERIAL, TYPE B-24" GEOTECHNICAL FABRIC FOR GROUND STABILIZATION

|  |                    |                   |           |
|--|--------------------|-------------------|-----------|
| FILE NAME =                                  | USER NAME = *USER* | DESIGNED - KMM    | REVISED - |
| ct:\pwork\dlz\ccooney\dms19784\63RESTORE.dgn |                    | DRAWN - LV        | REVISED - |
| PLOT SCALE = *SCALE*                         |                    | CHECKED - JDH     | REVISED - |
| PLOT DATE = 3/27/2014                        |                    | DATE - 03-31-2014 | REVISED - |

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**RESTORATION PLAN  
 63RD ST & YALE AVE, 63RD ST & WENTWORTH AVE**

SCALE: 1"=20' SHEET NO. OF SHEETS STA. TO STA.

| F.A.I. RTE.               | SECTION | COUNTY | TOTAL SHEETS       | SHEET NO. |
|---------------------------|---------|--------|--------------------|-----------|
| 94                        | 1920-B  | COOK   | 142                | 123       |
| ILLINOIS FED. AID PROJECT |         |        | CONTRACT NO. 60J15 |           |