

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	EAST FRONTAGE RD AT EXXON MOBIL CONTRACTORS GATE	EAST FRONTAGE RD AT EXXON MOBIL MAIN GATE
				TRAFFIC SIGNALS	TRAFFIC SIGNALS
				0021 URBAN	0021 URBAN
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2	1	1
Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	2	1	1

SUPPLEMENTAL CONSTRUCTION NOTES FOR CONTRACT 60P51

1. THESE TRAFFIC SIGNAL PLANS HAVE BEEN PREPARED "FOR INFORMATION ONLY" FOR CONTRACT 60P51 AND SHALL BE ONLY USED AS A GENERAL GUIDANCE IN PROVIDING SAFE AND EFFICIENT TRAFFIC SIGNAL STAGING OPERATIONS DURING THE CONSTRUCTION OF THE PROPOSED ROADWAY WORK.
2. TRAFFIC SIGNAL CONTRACTOR SHALL COORDINATE ALL THE WORK WITH THE ROADWAY CONTRACTOR TO ENSURE THE CORRECT STAGING OF THE SPAN WIRE TRAFFIC SIGNALS IS MAINTAINED.
3. TRAFFIC SIGNAL CONTRACTOR SHALL RELOCATE EXISTING SIGNAL HEADS TO ANY LOCATION ON THE SPAN WIRE IN ORDER TO MATCH ROADWAY STAGING OR AS DIRECTED BY THE ENGINEER. THE SPAN WIRE TRAFFIC SIGNAL SHALL REMAIN IN OPERATION DURING ALL SIGNAL HEADS RELOCATIONS. THIS WORK SHALL BE INCLUDED IN THE MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION PAY ITEM, AND THE PRICE SHALL INCLUDE ALL COSTS FOR MODIFICATIONS REQUIRED FOR TRAFFIC STAGING AS WELL AS ANY CHANGES TO THE SIGNAL PHASING. EACH INTERSECTION WILL BE PAID FOR SEPARATELY.
4. ALL THE TRAFFIC SIGNAL EQUIPMENT DISPLAYED IN THESE PLANS SHOULD BE CONSIDERED AS EXISTING AND SHOULD BE ALREADY INSTALLED AND OPERATIONAL IN THE FIELD. NO OTHER EQUIPMENT SHOULD BE NECESSARY UNDER THIS CONTRACT UNLESS OTHERWISE DIRECTED BY THE ENGINEER.

PERMANENT PAVEMENT MARKINGS SHALL BE CONSTRUCTED ACCORDING TO THE PAVEMENT MARKING PLANS ON SHEETS 66 TO 69 IN CONTRACT 60P51. AT NO TIME DOES THE CONTRACTOR HAVE THE AUTHORIZATION TO INSTALL PAVEMENT MARKINGS OUTSIDE OF THE RIGHT-OF-WAY AND TEMPORARY EASEMENTS.

DENOTES WORK INCLUDED IN THE COST OF OTHER ITEMS.

ADDED SHEET 5-27-14

TS*1

FILE NAME :	USER NAME : BillP	DESIGNED - LP	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES AND CONSTRUCTION NOTES EAST FRONTAGE RD AT EXXON MOBIL ENTRANCES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
S:\JUL\6300-0399\6345\045\Micro\CA00	Sheet\0129807-ahh\ts.dgn	DRAWN - LP	REVISED -			55	99-IAC-2	WILL	102	720	
Default	PLOT SCALE : 40.0000 ' / in.	CHECKED - JP	REVISED -			CONTRACT NO. 60P51					
	PLOT DATE : 5/27/2014	DATE - 05/21/2014	REVISED -			ILLINOIS FED. AID PROJECT					
					SCALE:	SHEET 1 OF 10 SHEETS		STA.	TO STA.		