



CONSTRUCTION NOTES

* FAR-OUT DETECTION SHALL BE PROVIDED AT APPROX. 250' FROM THE STOP BAR OR AS DIRECTED BY THE ENGINEER.

** CLOSE UP VIDEO DETECTION ZONES SHALL BE PROGRAMMED IN THE FIELD BY THE CONTRACTOR AND APPROVED BY THE ENGINEER. ZONE DIMENSIONS SHALL BE 36' BY 6', CENTERED ON LANES, OR AS DIRECTED BY THE ENGINEER.

THE TRAFFIC SIGNALS CONTRACTOR SHALL COORDINATE WITH THE ROADWAY CONTRACTOR TO ENSURE THE CORRECT STAGING OF THE TEMPORARY TRAFFIC SIGNALS.

WOOD POLE LOCATIONS ARE AS SHOWN ON SHEET 4-TS*4

EXXON MOBIL
CONTRACTORS GATE
STAGE 1A CONTRACT# 60P51

WIRELESS INTERCONNECT
TO EXXON MOBIL MAIN
GATE

A ADDED SHEET 5-27-14

| | | | | | | | | | | |
|--|--|--|--|---|---|---------------------------|----------|--------------------|--------------|-----------|
| FILE NAME #111111 | USER NAME BUIP | DESIGNED - LP | REVISED - LP 12/04/2012 | WILL COUNTY DEPARTMENT OF HIGHWAYS | TEMPORARY SPAN WIRE TRAFFIC SIGNAL INSTALLATION STAGE 1A (CONTRACT# 60P51) EAST FRONTAGE RD AT EXXON MOBIL CONTRACTORS GATE | F.A. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| DESIGNED - LP | DRAWN - LP | CHECKED - PB / SN | REVISED - JM 09/20/2013 | | | 55 | 99-IAC-2 | WILL | 102 | 72b |
| DATE - 11/16/2012 | REVISED - JM 10/02/2013 | DATE - 05/21/2014 | REVISED - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | TEMPORARY SPAN WIRE TRAFFIC SIGNAL INSTALLATION STAGE 1A EAST FRONTAGE RD AT EXXON MOBIL CONTRACTORS GATE | ILLINOIS FED. AID PROJECT | | CONTRACT NO. 60P51 | | |
| SCALE: 1 SHEET OF 10 SHEETS STA. TO STA. | SCALE: 1 SHEET OF 10 SHEETS STA. TO STA. | SCALE: 1 SHEET OF 10 SHEETS STA. TO STA. | SCALE: 1 SHEET OF 10 SHEETS STA. TO STA. | ILLINOIS FED. AID PROJECT | | | | | | |