



- * FAR-OUT DETECTION SHALL BE PROVIDED AT APPROX. 250' FROM THE STOP BAR OR AS DIRECTED BY THE ENGINEER.
 - ** CLOSE UP VIDEO DETECTION ZONES SHALL BE PROGRAMMED IN THE FIELD BY THE CONTRACTOR AND APPROVED BY THE ENGINEER. ZONE DIMENSIONS SHALL BE 36' BY 6', CENTERED ON LANES, OR AS DIRECTED BY THE ENGINEER.
- THE TRAFFIC SIGNALS CONTRACTOR SHALL COORDINATE WITH THE ROADWAY CONTRACTOR TO ENSURE THE CORRECT STAGING OF THE TEMPORARY TRAFFIC SIGNALS.

A ADDED SHEET 5-27-14

CONSTRUCTION NOTES:

1. PROPOSED UNDERGROUND ELECTRIC SERVICE LINE INSTALLATION PROVIDED BY EXXONMOBIL.
2. VIDEO DETECTION ZONES SHALL BE PROGRAMMED IN THE FIELD BY THE CONTRACTOR AND APPROVED BY THE ENGINEER. ZONE DIMENSIONS SHALL BE 36' BY 6', CENTERED ON LANES, OR AS DIRECTED BY THE ENGINEER.
3. THE CONTRACTOR SHALL PROVIDE (2) TWO TEMPORARY CHANGEABLE MESSAGE SIGNS, 500 FEET IN ADVANCE OF EACH PROPOSED SIGNAL ALONG THE EAST FRONTAGE RD TWO WEEKS PRIOR TO SIGNAL TURN ON.
4. THE TEMPORARY TRAFFIC SIGNAL HEADS SHALL BE PLACED AS INDICATED ON THE TEMPORARY TRAFFIC SIGNAL PLAN OR AS DIRECTED BY THE ENGINEER. APPROX. 150' FIFTY FT OF EXTRA CABLE HAS BEEN PROVIDED FOR EACH SIGNAL HEAD IN ORDER TO RELOCATE THE HEAD TO ANY POSITION ON THE SPAN WIRE AS ILLUSTRATED ON THE PLANS FOR CONSTRUCTION STAGING OR AS DIRECTED BY THE ENGINEER.
5. GU WIRES OR CONCRETE AS REQUIRED FOR STABILIZING THE WOOD POLES SHALL BE PROVIDED AND THE COST INCLUDED IN THE ASSOCIATED WOOD POLE PAY ITEM.
6. ELECTRICITY WILL BE PROVIDED FROM A SOURCE WITHIN THE EXXONMOBIL SITE.

NOTE:
THE TRAFFIC SIGNAL CONTROLLER EQUIPMENT FOR THIS PROJECT SHALL BE "EAGLE" TO MATCH THE EXISTING ADJACENT SYSTEM.

RESTORATION OF WORK AREA, RESTORATION OF THE TRAFFIC SIGNAL WORK AREA SHALL BE INCLUDED IN THE RELATED PAY ITEM SUCH AS FOUNDATION, CONDUIT, HANDHOLE, ETC., AND NO EXTRA COMPENSATION SHALL BE ALLOWED. ALL ROADWAY SURFACES SUCH AS SHOULDERS, MEDIAN, SIDEWALKS, PAVEMENT ETC. SHALL BE REPLACED IN KIND. ALL DAMAGE TO MOWED LAWNS SHALL BE REPLACED WITH AN APPROVED SOD, AND ALL DAMAGE TO UNMOWED FIELDS SHALL BE SEEDED IN ACCORDANCE WITH STANDARD SPECIFICATIONS 252 AND 250 RESPECTIVELY.

FILE NAME: 11/16/2012	USER NAME: RL2102	DESIGNED - LP	REVISED - LP 12/04/2012
PROJECT: 11/16/2012	PROJECT: 11/16/2012	DRAWN - LP	REVISED - LP 01/28/2013
PROJECT: 11/16/2012	PROJECT: 11/16/2012	CHECKED - PB / SN	REVISED - JW 09/20/2013
PROJECT: 11/16/2012	PROJECT: 11/16/2012	DATE - 11/16/2012	REVISED - JW 10/02/2013

**WILL COUNTY
DEPARTMENT OF HIGHWAYS**

**TEMPORARY SPAN WIRE TRAFFIC SIGNAL INSTALLATION
EAST FRONTAGE RD AT EXXON MOBIL MAIN GATE**

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
			10	9
CONTRACT NO.				

FILE NAME: 05/27/2014	USER NAME: B111P	DESIGNED - LP	REVISED -
PROJECT: 05/27/2014	PROJECT: 05/27/2014	DRAWN - LP	REVISED -
PROJECT: 05/27/2014	PROJECT: 05/27/2014	CHECKED - JP	REVISED -
PROJECT: 05/27/2014	PROJECT: 05/27/2014	DATE - 05/21/2014	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**TEMPORARY SPAN WIRE TRAFFIC SIGNAL INSTALLATION
EAST FRONTAGE RD AT EXXON MOBIL MAIN GATE**

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99-1AC-2	WILL	102	72n
CONTRACT NO. 60P51				