

SUMMARY OF QUANTITIES			URBAN		CONSTRUCTION TYPE CODE															
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0004 90% FED 10% STATE STATE URBAN	0021 90% FED 10% STATE TRAFFIC SIGNALS	0014 90% FED 10% STATE BRIDGE: MEDIAN WORK	0040 90% FED 10% STATE RETAINING WALL	0028 80% STATE 20% WILLOW SPRINGS SHARED PATH SIDEWALK	0021 100% WILLOW SPRINGS EVP											
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	310	310																
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	575	575																
550A0640	STORM SEWERS, CLASS A, TYPE 3 12"	FOOT	30	30																
550A0680	STORM SEWERS, CLASS A, TYPE 3 18"	FOOT	44	44																
550A0710	STORM SEWERS, CLASS A, TYPE 3 24"	FOOT	123	123																
550A4100	STORM SEWERS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 24"	FOOT	147	147																
55100500	STORM SEWER REMOVAL 12"	FOOT	1236	1236																
55100700	STORM SEWER REMOVAL 15"	FOOT	216	216																
55100900	STORM SEWER REMOVAL 18"	FOOT	16	16																
55101200	STORM SEWER REMOVAL 24"	FOOT	378	378																
58700300	CONCRETE SEALER	50 FT	3098				3098													
59100100	GEOCOMPOSITE WALL DRAIN	50 YD	220				220													
60107600	PIPE UNDERDRAINS 4"	FOOT	650	650																
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	35	35																
60200105	CATCH BASINS, TYPE A, 4' DIAMETER, TYPE I FRAME, OPEN LID	EACH	1	1																
60200805	CATCH BASINS, TYPE A, 4' -DIAMETER, TYPE B GRATE	EACH	1	1																

Rev. 6-3-14

Rev.

FILE NAME :	USER NAME : dora/001	DESIGNED -	REVISED -
6:\pwork\work\for\coray\neeh\0060753\142709-dra\p01a.dgn		DRAWN -	REVISED -
	PLOT SCALE : 100.0000' / 1"	CHECKED -	REVISED -
	PLOT DATE : 12/12/2013	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES  
IL 171 (ARCHER AVE) AT 104TH AVE. (FLAVIN ROAD)

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3565	B-N-5	COOK	129	7
SCALE:			SHEET NO. OF SHEETS	STA. TO STA.
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

14