SUMMARY OF QUANTITIES

URBAN

	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 0004 90% FED 10% STATE STATE URBAN	0021 90% FED 10% STATE TRAFFIC SIGNALS	0014 90% FED 10% STATE BRIDGE; MEDIAN WORK	0040 90% FED 10% STATE RETAINING WALL	0028 80% STATE 20% WILLOW SPRINGS SHARED PATH SIDEWALK	0021 100% WILLOW SPRINGS EVP
	60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	21	21					
	60203805	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1	1				
	60204505	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	1	1					
	60205040	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	1	1					
	60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4	4					
	60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	15	15	1				
Δ	60255410	CATCH BASINS TO BE CLEANED	EACH	27	27					
	60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1					
	60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	10	10					
	60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	1	1					
	60500040	REMOVING MANHOLES	EACH	15	15	1				
	60500050	REMOVING CATCH BASINS	EACH	5	5					
	60500060	REMOVING INLETS	EACH	22	22	1				

Δ 100% STATE (NP)

1 Rev. 6-3-14

FILE NAME = c:\pw_work\pwidot\paroynoah\d0160753\P142T09-sht-gen-details.dgn	USER NAME = paroynoah	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / In.	CHECKED -	REVISED -
	PLOT DATE = 12/12/2013	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
IL 171 (ARCHER AVE) AT 104TH AVE. (FLAVIN ROAD)

SCALE: | SHEET NO. OF SHEETS | STA. | TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3565	B-N-5	COOK	129	8
		CONTRACT NO. 60T24		

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT