

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE																	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0004 90% FED 10% STATE STATE URBAN	0021 90% FED 10% STATE TRAFFIC SIGNALS	0014 90% FED 10% STATE BRIDGE: MEDIAN WORK	0040 90% FED 10% STATE RETAINING WALL	0028 80% STATE 20% WILLOW SPRINGS SHARED PATH SIDEWALK	0021 100% WILLOW SPRINGS EVP												
40600895	CONSTRUCTING TEST STRIP	EACH	1	1																	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	198	198																	
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	16	16																	
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	357	75				282													
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	1454	1454																	
42001300	PROTECTIVE COAT	SQ YD	2364	2364																	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	5107	35				5072													
42400800	DETECTABLE WARNINGS	SQ FT	200	200																	
44000100	PAVEMENT REMOVAL	SQ YD	103	103																	
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	1849	1849																	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2264	2264																	
44000600	SIDEWALK REMOVAL	SQ FT	6857	6857																	
44002210	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 2 1/2"	SQ YD	110	110																	
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	205	205																	

Rev.

FILE NAME :	USER NAME :	DESIGNED :	REVISOR :	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				SUMMARY OF QUANTITIES IL 171 (ARCHER AVE) AT 104TH AVE. (FLAVIN ROAD)				F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN :	REVISOR :									3565	B-N-5	COOK	129	5
		CHECKED :	REVISOR :									CONTRACT NO. 60T24				
		DATE :	REVISOR :									FED. ROAD DIST. NO. 1 (ILLINOIS) FED. AID PROJECT				
PLOT SCALE = 100,000' / 1" / 1/4"		PLOT DATE = 12/12/2013		SCALE:		SHEET NO. OF SHEETS		STA. TO STA.								