

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE																		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0004 90% FED 10% STATE STATE URBAN	0021 90% FED 10% STATE TRAFFIC SIGNALS	0014 90% FED 10% STATE BRIDGE: MEDIAN WORK	0040 90% FED 10% STATE RETAINING WALL	0028 80% STATE 20% WILLOW SPRINGS SHARED PATH SIDEWALK	0021 100% WILLOW SPRINGS EVP													
* 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	2		2																	
* 87700240	STEEL MAST ARM ASSEMBLY AND POLE, 40 FT.	EACH	1		1																	
* 87700270	STEEL MAST ARM ASSEMBLY AND POLE, 46 FT.	EACH	1		1																	
* 87702574	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 36 FT. AND 54 FT.	EACH	1		1																	
* 87702719	STEEL MAST ARM ASSEMBLY & POLE WITH DUAL MAST ARMS, 46 FT. & 34 FT.	EACH	1		1																	
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	8		8																	
* 87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4		4																	
* 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	26		26																	
* 87800420	CONCRETE FOUNDATION, TYPE E 42-INCH DIAMETER	FOOT	42		42																	
* 88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	10		10																	
* 88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	5		5																	
*specialty items																						

Rev.

FILE NAME =	USER NAME = jpry/m00	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES IL 171 (ARCHER AVE) AT 104TH AVE. (FLAVIN ROAD)				F.A.U. RTE. 3565	SECTION B-N-5	COUNTY COOK	TOTAL SHEETS 129	SHEET NO. 13
c:\pwwork\jpry\m00\00160753\142709-01.dgn	PLOT SCALE = 100.0000' / 1in	DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT CONTRACT NO. 60T24		
	PLOT DATE = 12/12/2013	CHECKED -	REVISED -										
		DATE -	REVISED -										