



David Carl Puzey 5/13/14
 Expires 11/30/14

TOTAL BILL OF MATERIALS

ITEM	UNIT	QUANTITY
PROTECTIVE COAT	SO YD	1556
POLYMER CONCRETE	CU FT	6
BRIDGE DECK SCARIFICATION, 1/4"	SO YD	1023
BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/2"	SO YD	1023
HMA SURFACE COURSE, MIX "D", N70, 1 3/4"	TON	31
STRUCTURAL REPAIR OF CONCRETE > 5"	SO FT	6
STRUCTURAL REPAIR OF CONCRETE < 5"	SO FT	6
SLOPE WALL REMOVAL	SO YD	45
SLOPE WALL 4 INCH	SO YD	45
DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SO YD	18
PREFORMED JOINT SEAL 4"	FOOT	108
BRIDGE DECK GROOVING	SO YD	910
PROTECTIVE SHIELD	SO YD	285

FILE NAME *	USER NAME * puzanoskirb	DESIGNED 04/25/14 RP	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	BRIDGE PLANS IL 59 AT METRA RR (SN 016-2606)	F.A.P. RTE. 338	SECTION 110V-R-1-BR	COUNTY COOK	TOTAL SHEETS 28	SHEET NO. 6		
cr:\pwork\pedit\puzanoskirb\0835562	D134213-sht-plen.dgn	DRAWN 04/25/14 RP	REVISED -			SCALE:	SHEET 2 OF 6 SHEETS	STA. TO STA.	CONTRACT NO. 60W59			
Default	PLOT SCALE * 100.0000' / in.	CHECKED 04/24/14 AM	REVISED -			ILLINOIS FED. AID PROJECT						
	PLOT DATE * 5/12/2014	DATE 5/12/2014	REVISED -									