SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN 90% FED. 10% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 0021					
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	9925	9925					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
44004250	PAVED SHOULDER REMOVAL	SQ YD	2497	2497					
48101200	AGGREGATE SHOULDERS, TYPE B	TON	368	368					
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	10030	10030					
*63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	3388	3388					
*63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	10	10					
*63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	10	10					
63200310	GUARDRAIL REMOVAL	FOOT	3388	3388					
64200108	SHOULDER RUMBLE STRIPS, 8 INCH	FOOT	22209	22209					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3					
67100100	MOBILIZATION	L SUM	1	1					
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1					
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1					

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN 90% FED. 10% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 0021					
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1					
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	22923	22923					
*78200410	GUARDRAIL MARKERS, TYPE A	EACH	43	43					
*78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	10	10					
X2020110	GRADING AND SHAPING SHOULDERS	UNIT	92	92					
X4406030	PARTIAL DEPTH REMOVAL, TYPE I, 3"	SQ YD	4991	4991					
X4421000	PARTIAL DEPTH PATCHING	TON	839	839					
X4810200	AGGREGATE SHOULDER REMOVAL	CU YD	1858	1858					
*X7800815	HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINE - 4 INCH	FOOT	4692	4692					
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4					
Z0055400	RUMBLE STRIP	FOOT	11484	11484					
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	2000	2000					
* 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1					
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	5	5					

1 Rev. 6-3-14

* SPECIALTY ITEMS

☐ NON-PARTICIPATING ITEMS

FILE NAME = c:\pw_work\pwidot\sheed\d0036168\D34715-Dist1n.dgn	USER NAME = sheedd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES F.A.P. 557/ IL 72 (OAK KNOLL RD.)--DE KALB COUNTY LINE TO FRENCH RD.	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 1000.000 / in.	DRAWN -	REVISED -			557	2013-048I	KANE	24	3
	PLOT DATE = 5/24/2014	CHECKED -	REVISED -					CONTRACT NO. 60X02		
		DATE -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.	FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		