

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				95% STATE 5% VILLAGE OF CRETE	100% STATE	100% VILLAGE OF CRETE
				TRAFFIC SIGNALS 0021 URBAN	INTERCONNECT 0021 URBAN	EVP 0021 URBAN
88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	2	2		
88200200	TRAFFIC SIGNAL BACKPLATE, ALUMINUM	EACH	4	4		
88500100	INDUCTIVE LOOP DETECTOR	EACH	10	10		
88700200	LIGHT DETECTOR	EACH	3			3
88700300	LIGHT DETECTOR AMPLIFIER	EACH	1			1
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	20,860		20,860	
89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	145	145		
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1	1		
89502400	REMOVE EXISTING FLASHING BEACON INSTALLATION COMPLETE	EACH	4	4		
X0324085	EMERGENCY VEHICLE PRIORITY SYSTEM LINE SENSOR CABLE, NO. 20 3/C	FOOT	826			826
X0325714	FLASHING BEACON, POST MOUNTED, SOLAR POWERED INSTALLATION	EACH	4	4		
** X8570226	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1	1		
X8620200	UNINTERRUPTABLE POWER SUPPLY, SPECIAL	EACH	1	1		
X8710024	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM24F	FOOT	10,231		10,231	

14

* SPECIALTY ITEMS ** SPECIAL P CABINET

FILE NAME =	USER NAME = p001aohal	DESIGNED - LP / SS	REVISIONS -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES (SHEET 4 OF 5)				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\p001aohal\0301630\0125014-01-14.dgn		DRAWN - LP / SS	REVISIONS -		332	(10&0910-PT.1175-1114)	WILL	33	6				
PLOT SCALE = 100.0000' / 1"		CHECKED - SM	REVISIONS -						CONTRACT NO. 60X89				
PLOT DATE = 3/19/2014		DATE - 03/21/14	REVISIONS -		SCALE: NONE	SHEET NO.	OF SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT			