SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 0005					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	86	86					
25200110	SODDING, SALT TOLERANT	SQ YD	86	86					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	84	84					
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2209	2209					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	471	471					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	4640	4640					
42001300	PROTECTIVE COAT	SQ YD	115	115					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	48212	48212					
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	6993	6993					
44003100	MEDIAN REMOVAL	SQ FT	2271	2271					
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	1954	1954					
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	320	320					
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	40	40					

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		URBAN 100% STATE 0005					
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	150	150					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	655	655					
56109210	WATER VALVES TO BE ADJUSTED	EACH	3	3					
60255500	MANHOLES TO BE ADJUSTED	EACH	5	5					
60260100	INLETS TO BE ADJUSTED	EACH	5	5					
60262700	INLETS TO BE RECONSTRUCTED	EACH	2	2					
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	317	317					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70300100	SHORT TERM PAVEMENT MARKING	FOOT	10030	10030					
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	201	201					

FILE NAME = c:\pw_work\pw_ldot\phillipsdo\d0383\IUS52-sht-plan.dgn	USER NAME = phillipsdo	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 4/2/2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
U.S. ROUTE 52 (CHICAGO ST./IL ROUTE 53 TO LARAWAY ROAD)

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
852	(18&19)RS-6	WILL	26	3
		CONTRACT NO. 60Y02		

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT