

SUMMARY OF QUANTITIES				URBAN CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES				100% STATE TOTAL QUANTITIES URBAN 0005 CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 0005					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 0005				
78300200	RAISED REFLECTIVE PAVEMENT MARKER	EACH	600	600					* 88600100	DETECTOR LOOP, TYPE 1	FOOT	430	430				
	REMOVAL								* 81400200	HEAVY DUTY HANDHOLE	EACH	2	2				
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	372	372					* X8730810	ELECTRIC CABLE IN CONDUIT, CONOGA - 30003	FOOT	403	403				
* 89502376	REBUILD EXISTING HANDHOLE	EACH	2	2					* 81028770	UNDERGROUND CONDUIT, COILABLE NON METALLIC CONDUIT, 3" DIA.	FOOT	84.5	84.5				1
* 89502378	REBUILD EXISTING HANDHOLE TO HEAVY-DUTY HANDHOLE	EACH	2	2					* 81028730	UNDERGROUND CONDUIT, COILABLE NON METALLIC CONDUIT, 1 1/4" DIA.	FOOT	87.2	87.2				
X2020110	GRADING AND SHAPING SHOULDERS	UNIT	14	14					* X0301242	PIEZO AXLE SENSOR, CLASS 11	FOOT	4	4				
X4060110	BITUMINOUS MATERIALS (PRIME COAT)	POUND	34184	34184													
X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	8100	8100													
X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	3400	3400													
XZ043900	PREFORMED JOINT FILLER REMOVAL	FOOT	5120	5120													
Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	750	750													
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	47	47													
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4													
44022029	PARTIAL DEPTH REMOVAL, 3"	SQ YD	515	515													

* SPECIALTY ITEMS 1

Rev. 6-2-14