

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE		
CODE NO.	ITEM DESCRIPTION	UNIT		100% STATE 0005 QUANTITY	QUANTITY	QUANTITY
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	2,254	2,254		
25000110	SEEDING, CLASS 1A	ACRE	0.47	0.47		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	43	43		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	43	43		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	43	43		
25100630	EROSION CONTROL BLANKET	SQ YD	2,254	2,254		
25200200	SUPPLEMENTAL WATERING	UNIT	136	136		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	47	47		
28000510	INLET FILTERS	EACH	13	13		
28001100	TEMPORARY EROSION CONTROL BLANKET	SQ YD	2,254	2,254		
35101400	AGGREGATE BASE COURSE, TYPE B	TON	906	906		
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	1,393	1,393		
35800100	PREPARATION OF BASE	SQ YD	11,422	11,422		
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	7	7		
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	293	293		

\* INDICATES SPECIALTY ITEM

COPYRIGHT © 2006 BY BAXTER & WOODMAN, INC.  
 STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM  
 2500 N. WILSON AVENUE, SUITE 200, CHICAGO, IL 60642  
 TEL: (773) 399-2000 FAX: (773) 399-2001  
 WWW.BAXTERWOODMAN.COM



DESIGNED - DSH	REVISED -
DRAWN - UKB	REVISED -
CHECKED - LOH	REVISED -
DATE - 05-06-14	FILE - 140183_W0-1-S00.dgn

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

ILLINOIS YOUTH CENTER - ST. CHARLES  
SUMMARY OF QUANTITIES

SCALE: STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
347	2014-04R5	KANE	25	3
C-91-374-14			CONTRACT NO. 6CY37	
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				