

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE		
CODE NO.	ITEM DESCRIPTION	UNIT		100% STATE 0005 QUANTITY	QUANTITY	QUANTITY
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	340	340		
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	220	220		
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	1,478	1,478		
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	1,517	1,517		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	20	20		
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	154	154		
42001300	PROTECTIVE COAT	SQ YD	1,556	1,556		
44000100	PAVEMENT REMOVAL	SQ YD	422	422		
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	12,488	12,488		
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	179	179		
44000300	CURB REMOVAL	FOOT	411	411		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	5,387	5,387		
44000600	SIDEWALK REMOVAL	SQ FT	147	147		
44201682	CLASS D PATCHES, TYPE II, 3 INCH	SQ YD	46	46		

\* INDICATES SPECIALTY ITEM

COPYRIGHT © 2004 BY BAXTER & WOODMAN, INC.  
 STATE OF ILLINOIS PROFESSIONAL DESIGN FIRM  
 233 S. WASHINGTON ST., SUITE 200, CHICAGO, IL 60604  
 TEL: 312.467.1000 FAX: 312.467.1001  
 BAXTER & WOODMAN, INC. INCORPORATED  
 5/25/2004 5:45:53 PM

**BAXTER & WOODMAN**

DESIGNED - DSH	REVISED -
DRAWN - LKB	REVISED -
CHECKED - LDH	REVISED -
DATE - 05-06-14	FILE - 14C183_W0-1-500.dgn

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

ILLINOIS YOUTH CENTER - ST. CHARLES  
SUMMARY OF QUANTITIES

SCALE: STA. TO STA.

F.A. RFE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
347	2014-04RS	KANE	25	4
C-91-374-14		CONTRACT NO. 60Y37		
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				