HOT MIX ASPHALT SCHEDULE (I-80 RAMPS)

STATIONING	REMARKS	RAMP LANE LENGTH	RAMP LANE WIDTH	RAMP LANE AREA	X4060115 P BIT MATLS PR CT 2 APPL.	40600300 AGG PR CT	40603243 2¼", POLY HMA BC, IL-19.0 FG, N90	40603545 1½", POLY HMA SC, "D" N90	44000162 HMA SURF REM 3¼"	X4401198 HMA SURF REM VAR	RAMP HMA SHOULDER OUTSIDE (RT) WIDTH	OUTSIDE (RT) AREA	INSIDE (LT) WIDTH	INSIDE (LT) AREA	X4060115 P BIT MATLS PR CT 1 APPL.	40600300 AGG PR CT	40603310 1½", HMA SC "C" N50	44000153 HMA SURF REM 1"	3' AGG SHLDS DEPTH	48102100 AGG WEDGE SHLD T-B
		FEET	FEET	SQ. YD.	POUND	TON	TON	TON	SQ. YD	SQ. YD	FEET	SQ. YD.	FEET	SQ. YD.	POUND	TON	TON	SQ YD	FEET	TON
I-88 & I-80																				
SW RAMP 2																				
1370+00.00 - 1376+73.00	Includes Gore	673.00	VAR	1374.49	1855.56	2.06	173.19	115.46	1374.49		VAR	727.15			490.83	1.09	61.08	727.15	0.13	28.74
1376+73.00 - 1392+17.00	Mill & Res. 3.75"	1544.00	16.00	2744.89	3705.60	4.12	345.86	230.57	2744.89		6.00	1029.33	4.00	686.22	1158.00	2.57	144.11	1715.56	0.13	131.88
1392+17.00 - 1392+42.00	Taper 3.75"-3.25"	25.00	16.00	44.44	60.00	0.07	5.60	3.73		44.44	6.00	16.67	4.00	11.11	18.75	0.04	2.33	27.78	0.13	2.14
SW RAMP 1																				
1047+08.00 - 1047+33.00	Taper 3.25"-3.75"	25.00	16.00	400.00	540.00	0.60	50.40	33.60		400.00	6.00	16.67	4.00	11.11	18.75	0.04	2.33	27.78	0.13	2.14
1047+33.00 - 1049+69.00	Includes Gore	236.00	VAR	543.76	734.07	0.82	68.51	45.68	543.76		VAR	122.57			82.73	0.18	10.30	122.57	0.13	10.08
SOUTH WEAVE LANE 1																				
1049+69.00 - 1053+09.00	Mill & Res. 3.75"																			
1053+09.00 = 1060+00.00	STA EQUATION	670.00	VAR	1180.51	1593.69	1.77	148.74	99.16	1180.51		VAR	807.84			545.29	1.21	67.86	807.84	0.13	28.61
1060+00.00 - 1063+30.00	Mill & Res. 3.75"																			
SE RAMP 1																				
1063+30.00 - 1064+57.00	Includes Gore	127.00	VAR	349.58	471.93	0.52	44.05	29.36	349.58		VAR	75.01			50.63	0.11	6.30	75.01	0.13	5.42
1064+57.00 - 1076+64.00	Mill & Res. 3.75"	1207.00	16.00	2145.78	2896.80	3.22	270.37	180.25	2145.78		6.00	804.67	4.00	536.44	905.25	2.01	112.65	1341.11	0.13	103.10
1076+64.00 - 1076+89.00	Taper 3.75"-3.25"	25.00	16.00	44.44	60.00	0.07	5.60	3.73		44.44	6.00	16.67	4.00	11.11	18.75	0.04	2.33	27.78	0.13	2.14
SE RAMP 2																				
1109+56.00 - 1109+81.00	Taper 3.25"-3.75"	25.00	16.00	44.44	60.00	0.07	5.60	3.73		44.44	6.00	16.67	4.00	11.11	18.75	0.04	2.33	27.78	0.13	2.14
1109+81.00 - 1126+83.00	Mill & Res. 3.75"	1702.00	16.00	3025.78	4084.80	4.54	381.25	254.17	3025.78		6.00	1134.67	4.00	756.44	1276.50	2.84	158.85	1891.11	0.13	145.38
1126+83.00 - 1128+83.00	Includes Gore	200.00	VAR	557.80	753.03	0.84	70.28	46.86	557.80		VAR	129.64			87.50	0.19	10.89	129.64	0.13	8.54
SOUTH WEAVE LANE 2																				
1128+83.00 - 1137+87.00	Mill & Res. 3.75"	904.00	VAR	1882.69	2541.63	2.82	237.22	158.15	1882.69		6.00	602.67			406.80	0.90	50.62	602.67	0.13	38.61
NW RAMP 2																				
1329+21.00 - 1329+46.00	Taper 3.25"-3.75"	25.00	16.00	44.44	60.00	0.07	5.60	3.73		44.44	6.00	16.67	4.00	11.11	18.75	0.04	2.33	27.78	0.13	2.14
1329+46.00 - 1345+25.00	Mill & Res. 3.75"	1579.00	16.00	2807.11	3789.60	4.21	353.70	235.80	2807.11		6.00	1052.67	4.00	701.78	1184.25	2.63	147.37	1754.44	0.13	134.87
1345+25.00 - 1357+80.00	Includes Gore	1255.00	VAR	2015.98	2721.58	3.02	254.01	169.34	2015.98		VAR	1286.83			868.61	1.93	108.09	1286.83	0.13	53.60
NW RAMP 1																				
1003+75.00 - 1005+14.00	Includes Gore	139.00	VAR	454.22	613.20	0.68	57.23	38.15	454.22		VAR	88.00			59.40	0.13	7.39	88.00	0.13	5.94
1005+14.00 - 1015+93.00	Mill & Res. 3.75"	1079.00	16.00	1918.22	2589.60	2.88	241.70	161.13	1918.22		6.00	719.33	4.00	479.56	809.25	1.80	100.71	1198.89	0.13	92.16
1015+93.00 - 1016+18.00	Taper 3.75"-3.25"	25.00	16.00	44.44	60.00	0.07	5.60	3.73		44.44	6.00	16.67	4.00	11.11	18.75	0.04	2.33	27.78	0.13	2.14
NORTH WEAVE LANE 1																				
1109+51.00 - 1113+48.00	Mill & Res. 3.75"																			
1113+48.00 - 1000+00.00	STA EQUATION	772.00	VAR	1264.51	1707.09	1.90	159.33	106.22	1264.51		6.00	514.67			347.40	0.77	43.23	514.67	0.13	32.97
1000+00.00 - 1003+75.00	Mill & Res. 3.75"																			
NE RAMP 1																				
1098+41.00 - 1098+66.00	Taper 3.25"-3.75"	25.00	16.00	44.44	60.00	0.07	5.60	3.73		44.44	6.00	16.67	4.00	11.11	18.75	0.04	2.33	27.78	0.13	2.14
1098+66.00 - 1107+92.00	Mill & Res. 3.75"	926.00	16.00	1646.22	2222.40	2.47	207.42	138.28	1646.22		6.00	617.33	4.00	411.56	694.50	1.54	86.43	1028.89	0.13	79.10
1107+92.00 - 1109+51.00	Includes Gore	159.00	VAR	410.93	554.75	0.62	51.78	34.52	410.93		VAR	104.59			70.60	0.16	8.79	104.59	0.13	6.79
NORTH WEAVE LANE 2																				
1302+60.00 - 1311+51.00	Mill & Res. 3.75"	891.00	VAR	1061.44	1432.94	1.59	133.74	89.16	1061.44		VAR	1062.38			717.10	1.59	89.24	1062.38	0.13	38.05
RAMP A-B																				
1289+94.00 - 1290+54.00	Includes Gore																			
1290+54.00 = 1300+00.00	STA EQUATION	320.00	VAR	865.61	1168.58	1.30	109.07	72.71	865.61		VAR	275.83			186.18	0.41	23.17	275.83	0.13	13.67
1300+00.00 - 1302+60.00	Includes Gore																			
NE RAMP 2																				
1209+26.00 - 1211+16.00	Includes Gore	190.00	VAR	569.87	769.33	0.85	71.80	47.87	569.87		VAR	131.76			88.94	0.20	11.07	131.76	0.13	8.11
1211+16.00 - 1235+08.00	Mill & Res. 3.75"	2392.00	16.00	4252.44	5740.80	6.38	535.81	357.21	4252.44		6.00	1594.67	4.00	1063.11	1794.00	3.99	223.25	2657.78	0.13	204.32
1235+08.00 - 1235+33.00	Taper 3.75"-3.25"	25.00	16.00	44.44	60.00	0.07	5.60	3.73		44.44	6.00	16.67	4.00	11.11	18.75	0.04	2.33	27.78	0.13	2.14
I80 & OLD IL 2 RAMPS:																				
SOUTH WEAVE LANE 3																				
1280+00.00 - 1289+94.00	Mill & Res. 3.75"	994.00	VAR	1535.06	2072.33	2.30	193.42	128.94	1535.06				4.00	441.78	298.20	0.66	37.11	441.78	0.13	42.45
NORTH WEAVE LANE 3																				
1200+00.00 - 1209+26.00	Mill & Res. 3.75"	926.00	VAR	1672.74	2258.19	2.51	210.76	140.51	1672.74		6.00	617.33			416.70	0.93	51.86	617.33	0.13	39.55
RAMP C-D																				
1260+00.00 - 1266+73.00	Includes Gore	673.00	VAR	1361.13	1837.52	2.04	171.50	114.33	1361.13		VAR	548.08			369.95	0.82	46.04	548.08	0.13	28.74
1266+73.00 - 1274+23.00	Mill & Res. 3.75"	750.00	16.00	1333.33	1800.00	2.00	168.00	112.00	1333.33		6.00	500.00	4.00	333.33	562.50	1.25	70.00	833.33	0.13	64.06
			SUB TOTAL:		50875.02	56.53	4748.34	3165.56	36974.09	711.11					13621.13	30.27	1695.07	20179.45		1361.84