

**PATCHING SCHEDULE MAINLINE WB (CLASS A PATCHES, 11")**

STATION WB	REMARKS	PATCH LENGTH		44200565		44200569		44200571		44213000	44213200	44213204
		TYPE 2		TYPE 3		TYPE 4		PATCHING	SAW CUTS	TIE BARS		
		LT LANE (feet)	RT LANE (feet)	LT LANE (yd²)	RT LANE (yd²)	LT LANE (yd²)	RT LANE (yd²)	LT LANE (yd²)	RT LANE (yd²)	REINFORCEMENT (yd²)	(4W+?L) (foot)	3/4" (each)
805+68			18				24.0			24.0	66	
807+53		15				20.0				20.0	63	
808+02			52						69.3	69.3	100	25
811+50		65						86.7		86.7	113	32
817+16			11		14.7					14.7	59	
817+52		62						82.7		82.7	110	30
819+50			10		13.3					13.3	58	
822+05			17				22.7			22.7	65	
822+13		6		8.0						8.0	54	
828+93			25						33.3	33.3	73	12
829+39		22						29.3		29.3	70	10
831+27			23						30.7	30.7	71	11
1+94			42						56.0	56.0	90	20
2+15		6		8.0						8.0	54	
3+62		36						48.0		48.0	84	17
3+75			10		13.3					13.3	58	
5+29		50						66.7		66.7	98	24
8+79		20						26.7		26.7	68	9
8+89			8		10.7					10.7	56	
11+72			20						26.7	26.7	68	9
25+27			6		8.0					8.0	54	
85+08		6		8.0						8.0	54	
138+25		8		10.7						10.7	56	
138+00			6		8.0					8.0	54	
189+00		10	10	13.3	13.3					26.7	106	
200+28		8	8	10.7	10.7					21.3	104	
204+95		10	10	13.3	13.3					26.7	106	
299+25		8	8	10.7	10.7					21.3	104	
304+00		6	6	8.0	8.0					16.0	102	
368+00		8	16	10.7			21.3			32.0	112	
389+56		10	10	13.3	13.3					26.7	106	
402+02		6		8.0						8.0	54	
402+98			6		8.0					8.0	54	
476+26		6	6	8.0	8.0					16.0	102	
484+92			6		8.0					8.0	54	
485+11		38						50.7		50.7	86	18
506+19			6		8.0					8.0	54	
537+07			6		8.0					8.0	54	
540+55			50						66.7	66.7	98	24
540+72		6		8.0						8.0	54	
542+55			8		10.7					10.7	56	
543+00			10		13.3					13.3	58	
546+81		8	8	10.7	10.7					21.3	104	
600+63		46						61.3		61.3	94	22
600+86			6		8.0					8.0	54	
631+17			6		8.0					8.0	54	
631+29		8		10.7						10.7	56	
SUB TOTAL:				160.0	228.0	20.0	68.0	452.0	282.7	1,210.7	3522	263.0