

PATCHING SCHEDULE RAMPS (CLASS B PATCHES, 13")

STATION	REMARKS	PATCH LENGTH		TYPE 2		44201007	44201299	44213100	44213200	44213204
		LT LANE (feet)	RT LANE (feet)	LT LANE (yd ²)	RT LANE (yd ²)	DOWEL BARS, 1.5" (each)	PAVEMENT FABRIC (yd ²)	SAW CUTS (3W+1L) (foot)	TIE BARS 3/4" (each)	
OLD IL 2										
NW RAMP		6	6	5.3	5.3	24			54	
SW RAMP		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
SE RAMP		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
		8	8	7.1	7.1	24			56	
		8	8	7.1	7.1	24			56	
NE RAMP		16	16	14.2	14.2	24			64	
		10	10	8.9	8.9	24			58	
		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
IL 92										
NW RAMP		6	6	5.3	5.3	24			54	
		10	10	8.9	8.9	24			58	
SW RAMP		8	8	7.1	7.1	24			56	
SE RAMP		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
NE RAMP		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
MOLINE RD										
NW RAMP		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
		8	8	7.1	7.1	24			56	
SW RAMP		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
SE RAMP		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
NE RAMP		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
		6	6	5.3	5.3	24			54	
		10	10	8.9	8.9	24			58	
SUB TOTAL:				355.6	355.6	1,464.0	0.0		3,328.0	0.0

FILE NAME = C:\Projects\Rock_Island\64065.1-88_Cold Milling, pavement patching & HMA resurfacing
 USER NAME = diazeo
 DESIGNED -
 DRAWN -
 PLOT SCALE = 100.0000' / in.
 PLOT DATE = Wed Mar 19 11:14:44 2014
 CHECKED -
 DATE -
 REVISIONS:
 REVISION NO. DESCRIPTION DATE

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

PATCHING SCHEDULE

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.I. RTE. 88	SECTION (161-1) RS-1	COUNTY ROCK ISLAND	TOTAL SHEETS 104	SHEET NO. 41
CONTRACT NO. 64065		ILLINOIS FED. AID PROJECT		