PAVEMENT MARKING SCHEDULE (EAST BOUND RAMPS)

		64200116		78009004				78009006		78009008		78009012		X7830070	X7830074	X7830076	X7830078
		SHOULDER RUMBLE STRIPS, 16 INCH		MODIFIED URETHANE PAVEMENT MARKING - LINE 4"				MODIFIED URETHANE PAVEMENT MARKING - LINE 6"		MODIFIED URETHANE PAVEMENT MARKING - LINE 8"		MODIFIED URETHANE PAVEMENT MARKING - LINE 12"		GROOVING FOR RECESSED PAVEMENT MARKING 5"	GROOVING FOR RECESSED PAVEMENT MARKING 7"	GROOVING FOR RECESSED PAVEMENT MARKING 9"	GROOVING FOR RECESSED PAVEMENT MARKING 13"
STATIONING	REMARKS	FOOT		FOOT				FOOT		FOOT		FOOT		FOOT	FOOT	FOOT	FOOT
				WHITE SOLID		YELLOW SOLID		WHITE SKIP		WHITE		WHITE SOLID					
RAMPS (EAST BOUND)																	
I-80/I-88 SW RAMP 2 (EXIT)																	
1370+00.00 - 1373+05.00		305.0	RT	305.0	RT									305.0			
1373+05.00 - 1376+73.00		368.0	RT	368.0	RT					736.0	GORE SOL X2	176.0	GORE DIA	368.0		736.0	176.0
1376+73.00 - 1392+42.00		3138.0	RT & LT	1569.0	RT	1569.0	LT							3138.0			
I-80/I-88 SW RAMP 1 (ENTRANCE)																	
1047+08.00 - 1047+33.00		50.0	RT & LT	25.0	RT	25.0	LT							50.0			
1047+33.00 - 1049+69.00		236.0	RT	236.0	RT					472.0	GORE SOL X2			236.0		472.0	
I-80/I-88 S WEAVE LANE 1																	
1049+69.00 - 1053+09.00		340.0	RT	340.0	RT			85.0	LT					340.0	85.0		
1053+09.00 = 1060+00.00	STA. EQN.																
1060+00.00 - 1062+60.00		260.0	RT	260.0	RT			65.0	LT					260.0	65.0		
1062+60.00 - 1063+30.00		70.0	RT	70.0	RT					70.0	GORE SOL			70.0		70.0	
I-80/I-88 SE RAMP 1 (EXIT)																	
1063+30.00 - 1065+07.00		177.0	RT	177.0	RT					354.0	GORE SOL X2			177.0		354.0	
1065+07.00 - 1076+89.00		2364.0	RT & LT	1182.0	RT	1182.0	LT							2364.0			
I-80/I-88 SE RAMP 2 (ENTRANCE)																	
1109+56.00 - 1126+83.00		3454.0	RT & LT	1727.0	RT	1727.0	LT							3454.0			
1126+83.00 - 1128+83.00		200.0	RT	200.0	RT					400.0	GORE SOL X2			200.0		400.0	
I-80/I-88 S WEAVE LANE 2																	
1128+83.00 - 1137+87.00		904.0	RT	904.0	RT			226.0	LT					904.0	224.3		
OLD IL 2 SW RAMP (EXIT)																	
1137+87.00 - 1140+00.00		213.0	RT	213.0	RT					426.0	GORE SOL X2			213.0		426.0	
1140+00.00 = 1150+00.00	STA. EQN.																
1150+00.00 - 1151+82.00		182.0	RT	182.0	RT					364.0	GORE SOL X2	205.0	GORE DIA	182.0		364.0	205.0
1151+82.00 - 1166+00.00		2836.0	RT & LT	1418.0	RT	1418.0	LT							2836.0			
OLD IL 2 SE RAMP (ENTRANCE)																	
5401+88.00 - 5411+91.00		2006.0	RT & LT	1003.0	RT	1003.0	LT							2006.0			
5411+91.00 - 5414+16.00		225.0	RT	450.0	RT & LT					225.0	GORE SOL			450.0		225.0	
5414+16.00 - 5415+66.00		150.0	RT	150.0	RT					37.5	GORE SKIP			150.0		37.5	
5415+66.00 - 5423+50.00		784.0	RT	784.0	RT									784.0			
IL 92 SE RAMP (EXIT)																	
4975+48.00 - 4978+16.00		268.0	RT	268.0	RT									268.0			
4978+16.00 - 4982+11.00		395.0	RT	395.0	RT					790.0	GORE SOL X2	190.0	GORE DIA	395.0		790.0	190.0
4982+11.00 - 4998+66.00		3310.0	RT & LT	1655.0	RT	1655.0	LT							3310.0			
IL 92 NE RAMP (ENTRANCE)																	
5001+40.00 - 5009+69.00		1658.0	RT & LT	829.0	RT	829.0	LT							1658.0			
5009+69.00 - 5012+29.00		260.0	RT	520.0	RT & LT					260.0	GORE SOL			520.0		260.0	
5012+29.00 - 5014+69.00		240.0	RT	240.0	RT					60.0	GORE SKIP			240.0		60.0	
5014+69.00 - 5021+27.00		658.0	RT	658.0	RT									658.0			
MOLINE RD SE RAMP (EXIT)																	
5177+00.00 - 5180+08.00		308.0	RT	308.0	RT									308.0			
5180+08.00 - 5183+67.00		359.0	RT	359.0	RT					718.0	GORE SOL X2	182.0	GORE DIA	359.0		718.0	182.0
5183+67.00 - 5198+65.00		2996.0	RT & LT	1498.0	RT	1498.0	LT							2996.0			
MOLINE RD NE RAMP (ENTRANCE)																	
5201+26.00 - 5208+61.00		1470.0	RT & LT	735.0	RT	735.0	LT							1470.0			
5208+61.00 - 5211+58.00		297.0	RT	594.0	RT & LT					297.0	GORE SOL			594.0		297.0	
5211+58.00 - 5213+58.00		200.0	RT	200.0	RT					50.0	GORE SKIP			200.0		50.0	
5213+58.00 - 5220+19.50		661.5	RT	661.5	RT									661.5			
	SUB TOTAL:	31342.5		20483.5		11641.0		376.0		5259.5		753.0		32124.5	374.3	5259.5	753.0