

PAVEMENT MARKING SCHEDULE (EAST BOUND RAMPS)

STATIONING	REMARKS	78100100	78300200	70300100			70301000		
		RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	SHORT TERM PAVEMENT MARKING ** (3 APPLICATIONS)			WORK ZONE PAVEMENT MARKING REMOVAL		
		EACH	EACH	FOOT			SQ FT		
				RRPM REMARKS	WHITE RT EOP DIA	WHITE LT EOP DIA	YELLOW LT EOP DIA		
I-80/I-88 SW RAMP 2 (EXIT)									
1370+00.00 - 1373+05.00		15	15	RT	ONE-WAY CRYSTAL 20' o.c.	39			4
1373+05.00 - 1376+73.00		18	18	RT	ONE-WAY CRYSTAL 20' o.c.	45	45		10
1376+73.00 - 1382+96.00		18	18	GORE X2	ONE-WAY CRYSTAL 40' o.c.				
		16	16	LT	ONE-WAY AMBER 40' o.c.	75		75	17
I-80/I-88 SE RAMP 1 (EXIT)									
1062+60.00 - 1063+30.00		4	4	RT	ONE-WAY CRYSTAL 20' o.c.	9			1
		2	2	GORE	ONE-WAY CRYSTAL 40' o.c.				
1063+30.00 - 1065+07.00		9	9	RT	ONE-WAY CRYSTAL 20' o.c.	24	24		5
1065+07.00 - 1069+50.00		8	8	GORE X2	ONE-WAY CRYSTAL 40' o.c.				
		11	11	LT	ONE-WAY AMBER 40' o.c.	54		54	12
IL 2 SW RAMP (EXIT)									
1137+87.00 - 1140+00.00		11	11	RT	ONE-WAY CRYSTAL 20' o.c.	27	27		6
		10	10	GORE X2	ONE-WAY CRYSTAL 40' o.c.				
1140+00.00 = 1150+00.00	STATION EQUATION								
1150+00.00 - 1151+82.00		9	9	RT	ONE-WAY CRYSTAL 20' o.c.	24	24		5
		10	10	GORE	ONE-WAY CRYSTAL 40' o.c.				
1151+82.00 - 1157+40.00		14	14	LT	ONE-WAY AMBER 40' o.c.	69		69	15
IL 92 SE RAMP (EXIT)									
4975+48.00 - 4978+16.00		13	13	RT	ONE-WAY CRYSTAL 20' o.c.	33			4
4978+16.00 - 4982+11.00		20	20	RT	ONE-WAY CRYSTAL 20' o.c.	48	48		11
4982+11.00 - 4988+43.00		20	20	GORE X2	ONE-WAY CRYSTAL 40' o.c.				
		16	16	LT	ONE-WAY AMBER 40' o.c.	78		78	17
MOLINE RD SE RAMP (EXIT)									
5177+00.00 - 5180+08.00		15	15	RT	ONE-WAY CRYSTAL 20' o.c.	39			4
5180+08.00 - 5183+67.00		18	18	RT	ONE-WAY CRYSTAL 20' o.c.	45	45		10
		18	18	GORE X2	ONE-WAY CRYSTAL 40' o.c.				
5183+67.00 - 5189+49.00		15	15	LT	ONE-WAY AMBER 40' o.c.	72		72	16
	SUB TOTAL:	290	290			681	213	348	138

**SHORT TERM PAVEMENT MARKING FOR CENTERLINE SHALL BE PLACED ACCORDING TO 780001.

FILE NAME =	USER NAME = diaza	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PAVEMENT MARKING SCHEDULE	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
Default	0:\Projects\Rock_Island\64065-I-88_Cold Milling, pavement patching & HMA resurfacing	DRAWN to the Whiteside Co. Line\Mari's	REVISED FINAL\64065.dgn			88	(161-1) RS-1	ROCK ISLAND	104	50
	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -		SCALE:					
	PLOT DATE = Wed Mar 19 11:17:44 2014	DATE -	REVISED -		SHEET OF SHEETS	STA.	TO STA.			CONTRACT NO. 64065
										ILLINOIS FED. AID PROJECT