70300220
TEMPORARY PAVEMENT MARKING - LINE 4"

ALIGNMENT	STA FR	STA TO	OFFSET	DESCRIPTION	RAW	FOOT
TEMP SHARED USE PATH	04+50.00	07+59.00	RT	SOLID WHITE	309	309
TEMP SHARED USE PATH	08+18.00	08+52.00	LT	SOLID WHITE	48	48
TEMP SHARED USE PATH	16+40.00	17+90.00	RT	SOLID WHITE	150	150
TEMP SHARED USE PATH	16+34.00	18+42.00	LT	SOLID WHITE	206	206
RIVER DRIVE	1895+37.00	1896+25.00	RT	DOUBLE YELLOW	176	176
19TH ST	1899+90.00	1895+29.00	RT	SOLID WHITE	463	463
RIVER DR	3005+53.41	3012+32.92	LT/RT	SOLID YELLOW	1370.3	1371
RIVER DR	3005+57.51	3014+92.61	LT	SKIP-DASH	934.5	234
RIVER DR	3005+53.75	3014+92.61	RT	SKIP-DASH	939.5	235
RIVER DR	3012+29.76	3013+09.18	LT	SOLID YELLOW	79.4	80
RIVER DR	3013+06.01	3014+95.78	LT	SOLID YELLOW	386.3	387
RAMP (N-3)	172+50.00	173+28.27	LT	SKIP-DASH	71.0	18
RIVER DR	3016+20.13	3020+70.68	LT/RT	SOLID YELLOW	912.9	913
RIVER DR	3016+24.31	3020+75.00	LT	SKIP-DASH	450.7	113
RIVER DR	3016+24.31	3020+30.00	RT	SKIP-DASH	405.7	102
RIVER DR	3002+77.00	3004+72.00	RT	SKIP-DASH	195	49
23RD ST	3021+44.00	3021+45.00	RT	SKIP-DASH	150	38
RIVER DR	3022+31.00	3023+97.00	LT	SKIP-DASH	166	42
					TOTAL	4,934

70300240
TEMPORARY PAVEMENT MARKING - LINE 6"

ALIGNMENT	STA FR	STA TO	OFFSET		DESCRIPTION	RAW	FOOT
RIVER DRIVE	3004+83.82	3005+02.99	RT		SKIP-DASH	56.5	19
RIVER DRIVE	3005+13.00	3005+23.00	RT		SKIP-DASH	60	20
RIVER DRIVE	3002+77.00	3004+72.00	RT		SOLID WHITE	195	195
RIVER DRIVE	3021+44.00	3022+39.00	RT		SOLID WHITE	403	403
RIVER DRIVE	3021+82.00	3023+97.00	LT		SOLID WHITE	320	320
RIVER DRIVE	3005+52.51	3005+54.09	LT/RT		WHITE,XWALK	199.5	200
RIVER DRIVE	3011+99.53	3012+26.77	LT		WHITE,XWALK	79.8	80
RIVER DRIVE	3012+39.25	3012+82.85	LT		WHITE,XWALK	81.2	81
RIVER DRIVE	3015+70.82	3016+19.11	LT		WHITE,XWALK	91.3	91
RIVER DRIVE	3016+41.34	3016+61.52	LT		WHITE,XWALK	58.0	58
						TOTAL	1,467

70300250
TEMPORARY PAVEMENT MARKING - LINE 8"

ALIGNMENT	STA FR	STA TO	OFF SET	-	DESCRIPTION	RAW	FOOT
RIVER DR	3005+57.51	3008+22.54	LT	SOLID WHITE LANE LINE		265	265
RIVER DR	3007+36.32	3009+96.61	RT	SKIP-DASH		264	88
RIVER DR	3009+96.61	3014+92.61	RT	SOLID WHITE LANE LINE		496	496
RIVER DR	3013+09.18	3015+21.97	RT	SOLID WHITE LANE LINE		214	214
RIVER DR	3015+21.97	3014+45.00	RT	SOLID WHITE LANE LINE		233	233
RIVER DR	3014+36.74	3015+22.08	RT	SOLID WHITE LANE LINE		103	103
RIVER DR	3015+89.83	3016+40.25	RT	SOLID WHITE LANE LINE		57	57
RIVER DR	3015+93.98	3016+40.25	RT	SOLID WHITE LANE LINE		115	115
RIVER DR	3016+24.31	3020+75.00	LT	SOLID WHITE LANE LINE		451	451
RIVER DR	3016+24.31	3018+82.80	LT	SOLID WHITE LANE LINE		259	259
RIVER DR	3018+48.17	3020+68.05	RT	SOLID WHITE LANE LINE		220	220
RIVER DR	3018+09.73	3020+30.00	RT	SOLID WHITE LANE LINE		220	220
						TOTAL	2,720

70300260
TEMPORARY PAVEMENT MARKING - LINE 12"

ALIGNMENT	STA	STA	LT/RT	DESCRIPTION	-	-	FOOT
RIVER DR	3007+32.62	3014+92.61	LT/RT	STRIPE OUT FUTURE TURN LANE			893
RIVER DR	3014+36.74	3015+21.97	RT	PAINTED MEDIAN			274
RIVER DR	3015+89.83	3016+40.25	RT	PAINTED MEDIAN			298
RIVER DR	3016+17.82	3020+75.00	LT	STRIPE OUT FUTURE TURN LANE			296
						TOTAL	1,761

70300280
TEMPORARY PAVEMENT MARKING - LINE 24"

ALIGNMENT	STA FROM	OFFSET	LT/RT	STA TO	OFFSET	LT/RT	FOOT
RIVER DR	3005+57.51	3.44	LT	3005+57.51	41.91	LT	38.6
RIVER DR	3012+09.77	93.10	LT	3012+36.75	64.49	LT	39.3
RIVER DR	3012+43.58	60.96	LT	3012+79.32	61.54	LT	35.6
RIVER DR	3014+92.61	9.83	LT	3014+92.61	40.52	RT	24.0
RIVER DR	3015+76.74	47.93	RT	3015+92.93	47.93	RT	16.5
RIVER DR	3016+25.28	49.63	RT	3016+35.67	60.41	RT	15.0
RIVER DR	3016+24.31	40.00	LT	3016+24.31	1.73	LT	41.7
RIVER DR	3020+61.73	6.24	LT	3020+62.53	5.57	RT	11.8
						TOTAL	223

70300210
TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS

ALIGNMENT	STA	OFFSET		DESCRIPTION			SQ FT
RIVER DRIVE	3002+98.00	28.0	RT	RIGHT ARROW			15.6
RIVER DRIVE	3003+53.00	28.0	RT	RIGHT ARROW			15.6
RIVER DRIVE	3004+08.00	28.0	RT	RIGHT ARROW			15.6
RIVER DRIVE	3004+07.00	14.0	RT	RIGHT ARROW			15.6
RIVER DRIVE	3004+61.00	14.0	RT	RIGHT ARROW			15.6
RIVER DRIVE	3005+25.00	55.0	RT	THRU/LEFT			26
RIVER DRIVE	3005+25.00	69.0	RT	THRU/LEFT			26
RIVER DRIVE	3021+56.00	178.0	RT	RIGHT ARROW			15.6
RIVER DRIVE	3021+56.00	133.0	RT	RIGHT ARROW			15.6
RIVER DRIVE	3021+56.00	88.0	RT	RIGHT ARROW			15.6
RIVER DRIVE	3022+41.00	41.0	LT	RIGHT ARROW			15.6
RIVER DRIVE	3023+16.00	40.0	LT	RIGHT ARROW			15.6
RIVER DRIVE	3023+92.00	40.0	LT	RIGHT ARROW			15.6
RIVER DR	3005+79.88	6.7	LT	LEFT ARROW			15.6
RIVER DR	3006+93.74	7.6	LT	LEFT ARROW			15.6
RIVER DR	3008+06.31	7.3	LT	LEFT ARROW			15.6
RIVER DR	3013+19.25	47.2	RT	RIGHT ARROW			15.6
RIVER DR	3013+78.00	46.7	RT	RIGHT ARROW			15.6
RIVER DR	3014+36.74	48.5	RT	RIGHT ARROW			15.6
RIVER DR	3016+46.31	7.4	LT	LEFT ARROW			15.6
RIVER DR	3017+42.75	7.4	LT	LEFT ARROW			15.6
RIVER DR	3018+39.19	7.4	LT	LEFT ARROW			15.6
RIVER DR	3018+53.91	3.2	RT	LEFT ARROW			15.6
RIVER DR	3019+50.28	0.0	LT	LEFT ARROW			15.6
RIVER DR	3020+38.51	2.7	LT	LEFT ARROW			15.6
RIVER DR	3018+12.27	47.3	RT	RIGHT ARROW			15.6
RIVER DR	3019+08.69	45.5	RT	RIGHT ARROW			15.6
RIVER DR	3019+96.91	42.9	RT	RIGHT ARROW			15.6
						TOTAL	458

78008300
POLYUREA PAVEMENT MARKING TYPE II - LETTERS AND SYMBOLS

ALIGNMENT	STA	OFFSET	LT/RT	DESCRIPTION			SQ FT
RIVER DR	3005+79.88	6.7	LT	LEFT ARROW			15.6
RIVER DR	3006+93.74	7.6	LT	LEFT ARROW			15.6
RIVER DR	3008+06.31	7.3	LT	LEFT ARROW			15.6
RIVER DR	3013+19.25	47.2	RT	RIGHT ARROW			15.6
RIVER DR	3013+78.00	46.7	RT	RIGHT ARROW			15.6
RIVER DR	3014+36.74	48.5	RT	RIGHT ARROW			15.6
RIVER DR	3016+46.31	7.4	LT	LEFT ARROW			15.6
RIVER DR	3017+42.75	7.4	LT	LEFT ARROW			15.6
RIVER DR	3018+39.19	7.4	LT	LEFT ARROW			15.6
RIVER DR	3018+53.91	3.2	RT	LEFT ARROW			15.6
RIVER DR	3019+50.28	0.0	LT	LEFT ARROW			15.6
RIVER DR	3020+38.51	2.7	LT	LEFT ARROW			15.6
RIVER DR	3018+12.27	47.3	RT	RIGHT ARROW			15.6
RIVER DR	3019+08.69	45.5	RT	RIGHT ARROW			15.6
RIVER DR	3019+96.91	42.9	RT	RIGHT ARROW			15.6
						TOTAL	234

78008310
POLYUREA PAVEMENT MARKING TYPE II - LINE 4"

ALIGNMENT	STA FROM	STA TO	LT/RT	# LINES	LINE TYPE	RAW LENGTH	FOOT
RIVER DR	3005+53.41	3012+32.92	LT/RT	1	SOLID YELLOW	1370.3	1,371
RIVER DR	3005+57.51	3014+92.61	LT	1	SKIP-DASH	934.5	234
RIVER DR	3005+53.75	3014+92.61	RT	1	SKIP-DASH	939.5	235
RIVER DR	3012+29.76	3013+09.18	LT	1	SOLID YELLOW	79.4	80
RIVER DR	3013+06.01	3014+95.78	LT	1	SOLID YELLOW	386.3	387
Ramp (N-3)	172+50.00	173+28.27	LT	1	SKIP-DASH	71.0	18
RIVER DR	3016+20.13	3020+70.68	LT/RT	1	SOLID YELLOW	912.9	913
RIVER DR	3016+24.31	3020+75.00	LT	1	SKIP-DASH	450.7	113
RIVER DR	3016+24.31	3020+30.00	RT	1	SKIP-DASH	405.7	102
RIVER DR	3002+77.00	3004+72.00	RT	1	SKIP-DASH	195	49
23RD ST	3021+44.00	3021+45.00	RT	1	SKIP-DASH	150	38
RIVER DR	3022+31.00	3023+97.00	LT	1	SKIP-DASH	166	42
						TOTAL	3,582

78008330
POLYUREA PAVEMENT MARKING TYPE II - LINE 6"

ALIGNMENT	STA FROM	STA TO	LT/RT	# LINES	LINE TYPE	LOCATION	FOOT
RIVER DR	3005+52.51	3005+54.09	LT/RT	2	WHITE,XWALK	RIVER/191TH	199.5
RIVER DR	3011+99.53	3012+26.77	LT	2	WHITE,XWALK	RIVER/PR RD-G STUB	79.8
RIVER DR	3012+39.25	3012+82.85	LT	2	WHITE,XWALK	RIVER/PR RD-G STUB	81.2
RIVER DR	3015+70.82	3016+19.11	LT	2	WHITE,XWALK	RIVER/PR RD-H STUB	91.3
RIVER DR	3016+41.34	3016+61.52	LT	2	WHITE,XWALK	RIVER/PR RD-H STUB	58.0
						TOTAL	510

78008340
POLYUREA PAVEMENT MARKING TYPE II - LINE 8"

ALIGNMENT	STA FROM	STA TO	LT/RT	LINE TYPE	RAW LENGTH	FOOT
RIVER DR	3005+57.51	3008+22.54	LT	SOLID WHITE LANE LINE	265	265
RIVER DR	3007+36.32	3009+96.61	RT	SKIP-DASH	264	88
RIVER DR	3009+96.61	3014+92.61	RT	SOLID WHITE LANE LINE	496	496
RIVER DR	3013+09.18	3015+21.97	RT	SOLID WHITE LANE LINE	214	214
RIVER DR	3015+21.97	3014+45.00	RT	SOLID WHITE LANE LINE	233	233
RIVER DR	3014+36.74	3015+22.08	RT	SOLID WHITE LANE LINE	103	103
RIVER DR	3015+89.83	3016+40.25	RT	SOLID WHITE LANE LINE	57	57
RIVER DR	3015+93.98	3016+40.25	RT	SOLID WHITE LANE LINE	115	115
RIVER DR	3016+24.31	3020+75.00	LT	SOLID WHITE LANE LINE	451	451
RIVER DR	3016+24.31	3018+82.80	LT	SOLID WHITE LANE LINE	259	259
RIVER DR	3018+48.17	3020+68.05	RT	SOLID WHITE LANE LINE	220	220
RIVER DR	3018+09.73	3020+30.00	RT	SOLID WHITE LANE LINE	220	220
					TOTAL	2,720

78008350
POLYUREA PAVEMENT MARKING TYPE II - LINE 12"

ALIGNMENT	STA FROM	STA TO	LT/RT	LINE TYPE		FOOT
RIVER DR	3007+32.62	3014+92.61	LT/RT	STRIPE OUT FUTURE TURN LANE		893
RIVER DR	3014+36.74	3015+21.97	RT	PAINTED MEDIAN		274
RIVER DR	3015+89.83	3016+40.25	RT	PAINTED MEDIAN		298
RIVER DR	3016+17.82	3020+75.00	LT	STRIPE OUT FUTURE TURN LANE		296
					TOTAL	1,761

Copyright Hanson Professional Services Inc.
HANSON
Hanson Professional Services Inc.

LAYOUT	CBP	2/22/2013
DRAWN	CBP	2/22/2013
REVIEWED	AAP	3/5/2014

SCH0-08

FILE NAME = D2PACKE-HPS-sht-schedule001.dgn	USER NAME = petke00954	DESIGNED - CBP	REVISED -
		DRAWN - CBP	REVISED -
	PLOT SCALE =	CHECKED - AAP	REVISED -
	PLOT DATE = 03\25\2014	DATE - 3/7/2014	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.U RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5756	(81-1)M	ROCK ISLAND	217	30
		CONTRACT NO. 64J68		
		ILLINOIS FED. AID PROJECT		