PROPOSED AND RELOCATION SIGN SCHEDULE

SIGN PLAN SHEET NUMBER	DESCRIPTION	SIGN DESIGNATION	SIGN CODE	ALIGNMENT NAME	S TA TION	OFFSET	PANEL WIDTH	PANEL HEIGHT	POST ONE LENGTH	POST TWO LENGTH	MOUNTING TYPE TS - BS - LP - TS - WP-SM	50800105 REINFORCEMENT BARS	72000100 SIGN PANEL TYPE 1	72000300 SIGN PANEL TYPE 3	72400600 RELOCATE SIGN PANEL ASSEMBLY - TYPE B	72400730 RELOCATE SIGN PANEL TYPE 3	72700100 S TRUC TURAL S TEEL SIGN SUPPORT - BREAKAWAY	72800100 TELESCOPING STEEL SIGN SUPPORT	73000100 WOOD SIGN SUPPORT	73400100 CONCRETE FOUNDATION
							FOOT	FOOT	FOOT	FOOT		POUND	SQ FT	SQ FT	EACH	SQ FT	POUND	FOOT	FOOT	CU YD
SGN-03	KEEP RIGHT	R4-7	EB-3-TS-301A-P	RIVER DRIVE	3004+64	9.81' LT	2.00	2.50	13.00		TS		5					13		<u> </u>
SGN-03	KEEP RIGHT	R4-7	EB-3-TS-301-P	RIVER DRIVE	3005+61	1.50' RT	2.00	2.50	13.00		TS		5					13		
SGN-03	JUNCTION	M2-1(I) M1-1	EB-3-TS-302-P EB-3-TS-303-P	RIVER DRIVE	3006+00 3006+00	37' RT 37' RT	1.75	1.25 2.00	16.00		TS		2					16		+
	RIVERWAY TRAILS, WATER TAXI, VISITOR	101 1-1	WB-3-TS-201-RL				2.50	0.67					4							+
SGN-04	MOUNE PLACARD		WB-3-TS-202-RL	RIVER DRIVE	3006+55	46' LT	3.00	3.00			TS				1		-			-
SGN-04	NO PARKING	R8-3	EB-3-TS-303A-P	RIVER DRIVE	3006+71	38' RT	2.00	2.00	16.00		TS		4					16		+
SGN-04	NO PARKING	R8-3	EB-3-WP-303B-P	RIVER DRIVE	3007+98	46' LT	2.00	2.00	12.00		TS		4					12		+
SGN-04	SPEED LIMIT 30	R2-1	EB-3-TS-304-P	RIVER DRIVE	3008+00	41' RT	2.50	3.00	15.00		TS		8					15		-
	EAST	M3-2(I)	WB-3-TS-305-P	RIVER DRIVE	3008+20	46' LT	2.00	1.00					2							
SGN-04	INTERSTATE ROUTE SIGN	M1-1	WB-3-TS-306-P	RIVER DRIVE	3008+20	46' LT	2.00	2.00	17.00		TS		4					17		
	ADVANCE TURN ARROW	M5-1(I)	WB-3-TS-307-P	RIVER DRIVE	3008+20	46' LT	1.75	1.25					2							
SGN-05	J. DEERE PAV, I WIRELESS, MOLINE, ROCK		WB-3-TS-209-RL	RIVER DRIVE	3013+18	45.58' LT	2.50	0.67			TS				1					
001100	MOLINE PLACARD		WB-3-TS-210-RL		5015+10	40.00 LT	3.00	3.00			15									
SGN-05	I-74/US 6 WEST DAVENPORT (PROPOSED)		EB-3-BS-211A-P	RIVER DRIVE	3013+11	61' RT	12.00	9.00	*	*	BS	156		108			*			*
SGN-05	I-74/US 6 WEST DAVENPORT (RELOCATED)		EB-3-WP-211B-RL	RIVER DRIVE	3013+00	61' RT			18.50	18.50	WP					84			37	1
SGN-05	OBJECT MARKER	OM4-1	WB-3-TS-310A-P	RIVER DRIVE	3012+17	99.44' LT	1.50	1.50	14.00		TS		2.25					14		1
SGN-05	OBJECT MARKER	OM 4-1	WB-3-TS-310B-P	RIVER DRIVE	3012+25	92.27' LT	1.50	1.50	14.00		TS		2.25					14		1
SGN-05	OBJECT MARKER	OM 4-1	WB-3-TS-310C-P	RIVER DRIVE	3012+33	85.84' LT	1.50	1.50	14.00		TS		2.25					14		+
SGN-05	OBJECT MARKER	OM4-1	WB-3-TS-310D-P	RIVER DRIVE	3012+40	78.49' LT	1.50	1	14.00		TS		2.25					14		+
		R5-1		RIVER DRIVE				1.50			TS		9							+
SGN-05	DO NOT ENTER		WB-3-TS-310E-P		3012+45	73.97' LT	3.00	3.00	15.00				Ū,					15		
SGN-05	OBJECT MARKER	OM4-1	WB-3-TS-310F-P	RIVER DRIVE	3012+53	72.58' LT	1.50	1.50	14.00		TS		2.25					14		
SGN-05	OBJECT MARKER	OM4-1	WB-3-TS-310G-P	RIVER DRIVE	3012+64	59.18' LT	1.50	1.50	14.00		TS		2.25					14		
SGN-05	OBJECT MARKER	OM4-1	WB-3-TS-310H-P	RIVER DRIVE	3012+75	65.69' LT	1.50	1.50	14.00		TS		2.25					14		
SGN-05	DO NOT ENTER	R5-1	WB-3-TS-310I-P	RIVER DRIVE	3012+81	62.71' LT	3.00	3.00	15.00		TS		9					15		
SGN-05	NO LEFT TURN	R3-1	EB-3-TS-310J-P	RIVER DRIVE	3012+25	12.5' LT	2.50	2.50	15.00		TS		6.25					15		
SGN-05	NO RIGHT TURN	R3-1	WB-3-TS-310K-P	RIVER DRIVE	3013+18	45.58' LT	2.50	2.50	15.00		TS		6.25							
SGN-05	NO LEFT TURN	R3-1	EB-3-TS-311A-P	RIVER DRIVE	3014+88	12.42' LT	2.50	2.50	15.00		TS		6.25					15		
SGN-05	DO NOT ENTER (SEE NOTE BELOW)	R5-1	WB-3-TS-311B-P	RIVER DRIVE	3015+86	78.71' LT	3.00	3.00	15.00		TS		18					15		-
SGN-05	OBJECT MARKER (SEE NOTE BELOW)	OM4-1	WB-3-TS-311C-P	RIVER DRIVE	3015+91	80.18' LT	1.50	1.50	14.00		TS		4.5					13		
SGN-05	OBJECT MARKER (SEE NOTE BELOW)	OM4-1	WB-3-TS-311D-P	RIVER DRIVE	3016+00	78.60' LT			14.00		TS		4.5							+
							1.50	1.50										14		
SGN-05	OBJECT MARKER (SEE NOTE BELOW)	OM4-1	WB-3-TS-311E-P	RIVER DRIVE	3016+09	76.96' LT	1.50	1.50	14.00		TS		4.5					14		
SGN-05	OBJECT MARKER (SEE NOTE BELOW)	OM4-1	WB-3-TS-311F-P	RIVER DRIVE	3016+19	75.51' LT	1.50	1.50	14.00		TS		4.5					14		
SGN-05	DO NOT ENTER (SEE NOTE BELOW)	R5-1	WB-3-TS-311G-P	RIVER DRIVE	3016+24	72.98' LT	3.00	3.00	15.00		TS		18					15		
SGN-05	DO NOT ENTER (SEE NOTE BELOW)	R5-1	WB-3-TS-311H-P	RIVER DRIVE	3016+27	73.18' LT	3.00	3.00	15.00		TS		18					15		
SGN-05	OBJECT MARKER (SEE NOTE BELOW)	OM 4-1	WB-3-TS-311I-P	RIVER DRIVE	3016+30	78.04' LT	1.50	1.50	14.00		TS		4.5					14		
SGN-05	OBJECT MARKER (SEE NOTE BELOW)	OM4-1	WB-3-TS-311J-P	RIVER DRIVE	3016+38	82.72' LT	1.50	1.50	14.00		TS		4.5					14		
SGN-05	OBJECT MARKER (SEE NOTE BELOW)	OM4-1	WB-3-TS-311K-P	RIVER DRIVE	3016+46	87.69' LT	1.50	1.50	14.00		TS		4.5					14		1
SGN-05	NO RIGHT TURN	R3-1	WB-3-TS-312A-P	RIVER DRIVE	3017+36	57.08' LT	2.50	2.50	15.00		TS		6.25					15		1
	ONE WAY	R6-1L	WB-3-TS-308-P	RIVER DRIVE	3012+90	45.58' LT	3.00	1.00					3							1
SGN-05	ONE WAY	R6-1R	WB-3-TS-309-P	RIVER DRIVE	3012+90	45.58' LT	3.00	1.00	17.00		TS		3					17		1
	DO NOT ENTER	R5-1	WB-3-TS-310-P	RIVER DRIVE	3012+90	45.58' LT	3.00	3.00	1				9							1
SGN-05	KEEP RIGHT	R4-7	EB-3-TS-311-P	RIVER DRIVE	3013+16	12.52' LT	2.00	2.50	13.00		TS		5					13		
SGN-05	KEEP RIGHT	R4-7	EB-3-TS-312-P	RIVER DRIVE	3016+30	5.90' RT	2.00	2.50	13.00		TS		5					13		
SGN-06	I-74/US 6 WEST DAVENPORT (PROPOSED)		WB-3-BS-222A-P	RIVER DRIVE	3020+30	64' LT	12.00	9.00	*	*	BS	156		108			*			*
SGN-06	I-74/US 6 WEST DAVENPORT (RELOCATED)		WB-3-WP-222B-RL	RIVER DRIVE	3020+40	64' LT			18.50	18.50	WP					84			37	
SGN-06	NO PARKING	R8-3	EB-20-TS-312A-P	20TH ST	36+31	19' LT	2.00	2.00	14.00		TS		4					14		
SGN-06	NO PARKING	R8-3	WB-20-TS-312B-P	20TH ST	36+37	19' RT	2.00	2.00	14.00		TS		4					14		
SGN-06	SPEED LIMIT 30	R2-1	WB-3-TS-313-P	RIVER DRIVE	3019+00	58' LT	2.50	3.00	18.00		TS		8					18		
SGN-06	NO RIGHT TURN	R3-1	WB-3-TS-313A-P	RIVER DRIVE			2.50	3.00			TS		8							
SGN-06	KEEP RIGHT	R4-7	WB-3-TS-316-P	RIVER DRIVE	3020+60	9.96' LT	2.00	2.50	13.00		TS		5					13		+
SGN-07	FORM SINGLE LINE		NB-R3N-TS-214-RL	RAMP (3-N)	369+35	37' RT	4.00	4.00			TS				1					
SGN-07	RIVERWAY TRAILS, WATER TAXI, VISITOR		SB-R3S-TS-216-RL	RAMP (N-3)	173+01	6' RT	4.00	4.00			TS				1					
0000	MOLINE PLACARD		SB-R3S-TS-217-RL	10-1011 (14-5)	11.0101	URI	3.67	1.50			15		[' '					
0.011.07	RIVERWAY TRAILS, WATER TAXI, VISITOR		SB-R3S-TS-218-RL		470.00	0011 -	4.00	4.00			T 0									1
SGN-07	MOLINE PLACARD		SB-R3S-TS-219-RL	RAMP (N-3)	172+98	36' LT	3.67	1.50			TS				1		1			1
SGN-07	DO NOT ENTER	R5-1	EB-R3S-TS-317-P	RAMP (N-3)	173+97	36' LT	3.00	3.00	15.00		TS		9					15		1
										TOTAL		310	246	216	5	168	1110	535	74	2.8

LAYOUT MPV 7/1/2011 DRAWN MPV 2/5/2013 REVIEWED MTH 3/14/2014

THE SIGNS AND POSTS LOCATED AT THE RAMP TERMINATION POINTS SHALL BE REMOVED WHILE THE STABILIZED CONSTRUCTION ENTRANCE IS IN USE. THE SIGNS AND POSTS SHALL BE REINSTALLED AFTER 20TH STREET CONSTRUCTION IS COMPLETE AND THE STABILIZED CONSTRUCTION ENTRANCE IS REMOVED. 2.

LT M									SGN-02
FILE NAME =	USER NAME = petke00954	DESIGNED - MPV	REVISED -			SIGNING PLAN	F.A.U	SECTION	COUNTY TOTAL SHEET
D2PACKE-HPS-sht-sign002.dgn		DRAWN - MPV	REVISED -	STATE OF ILLINOIS		SIGN SCHEDULES	5756	(81-1)M	ROCK ISLAND 217 120
	PLOT SCALE =	CHECKED - MTH	REVISED -	DEPARTMENT OF TRANSPORTATION		PROPOSED AND RELOCATED SIGNS			CONTRACT NO. 64J68
	PLOT DATE = 03\25\2014	DATE - 3/7/2014	REVISED -		SCALE:	SHEET NO. OF SHEETS STA. TO STA.		ILLINOIS FED.	AID PROJECT