

INDEX OF SHEETS

1	COVER SHEET
2	INDEX OF SHEETS & STATE STANDARDS & GENERAL NOTES
3	SUMMARY OF QUANTITIES
4	MAINTENANCE OF PEDESTRIAN TRAFFIC DETAILS
5 - 10	SUBSTRUCTURE REPAIR DETAILS SN 098-0051 & 098-0052
11	GENERAL PLAN AND ELEVATION SN 098-0051
12	JOINT REMOVAL & REPLACEMENT DETAILS AT ABUTMENTS SN 098-0051
13	PREFORMED JOINT STRIP SEAL AT ABUTMENTS SN 098-0051
14	FINGER PLATE REMOVAL & REPLACEMENT DETAILS AT PIER 3 SN 098-0051
15 - 16	FINGER PLATE JOINT DETAILS AT PIER 3 SN 098-0051
17	BAR SPLICER ASSEMBLY AND MECHANICAL SPLICER DETAILS SN 098-0051
18	GENERAL PLAN AND ELEVATION SN 098-0052
19	JOINT REMOVAL & REPLACEMENT DETAILS SN 098-0052
20	PREFORMED JOINT STRIP SEAL SN 098-0052
21	BAR SPLICER ASSEMBLY AND MECHANICAL SPLICER DETAILS SN 098-0052
* 22 - 32	EXISTING PLAN SHEETS FOR SN 098-0051 & 098-0052
33	TRAFFIC CONTROL FOR ROAD CLOSURE (DIST STD 40.1)

△
* Added 32A, 32B.

STATE STANDARDS

701006 - 05	OFF-RD OPERATIONS, 2L, 2W, 15' (4.5 m) TO 24" (600 mm) FROM PAVEMENT EDGE
701201 - 04	LANE CLOSURE, 2L, 2W, DAY ONLY, FOR SPEEDS ≥ 45 MPH
701301 - 04	LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
701311 - 03	LANE CLOSURE 2L, 2W MOVING OPERATIONS - DAY ONLY
701801 - 05	SIDEWALK, CORNER OR CROSSWALK CLOSURE
701901 - 03	TRAFFIC CONTROL DEVICES
720011 - 01	SIGN PANEL MOUNTING DETAILS
728001 - 01	TELESCOPING STEEL SIGN SUPPORT
729001 - 01	APPLICATIONS OF TYPES A & B METAL POSTS (FOR SIGNS & MARKERS)

GENERAL NOTES

All Borrow/Waste/Use sites must be approved by the Department prior to removing any material from the project or initiating any earthmoving activities, including temporary stockpiling outside the limits of construction.

The Contractor shall be responsible for protecting utility property during construction operations as outlined in Article 107.31 of the Standard Specifications. A minimum of 48 hours advance notice is required for non-emergency work. The JULIE number is 800-892-0123. The following listed utilities located within the project limits or immediately adjacent to the project construction limits are members of JULIE:

Electric:
COMMONWEALTH EDISON COMPANY
ATTN: NORA FERNANDEZ
123 ENERGY AVENUE
ROCKFORD, IL 61109

CITY OF ROCK FALLS
ATTN: DICK SIMON
1109 INDUSTRIAL PATK ROAD
ROCK FALLS, IL 61071

Telephone:
AT&T
ATTN: DAVID CREEN
2800 7TH STREET
MOLINE, IL 61265

US SPRINT
ATTN: JAMES BURTON
5600 N RIVER ROAD/
ROSEMONT, IL 60018

Water:
IL AMERICAN WATER COMPANY
304 SECOND AVENUE
STERLING, IL 61081

CITY OF ROCK FALLS
ATTN: TED PADILLA
603 WEST 10TH STREET
ROCK FALLS, IL 610071

Sewer:
CITY OF ROCK FALLS
ATTN: EDWARD COX
603 WEST 10TH STREET
ROCK FALLS, IL 61071

CITY OF STERLING
ATTN: SCOTT SHUMARD
212 3RD AVENUE
STERLING, IL 61081

Gas:
NICOR GAS CO.
ATTN: CONSTANCE LANE
1844 FERRY ROAD
NAPERVILLE, IL 60563

CATV:
COMCAST CABLE
ATTN: MICHAEL OWENS
4450 KISHWAUKEE STREET
ROCKFORD, IL 61109

Communications:
G4S TECHNOLOGY, LLC
1428 SHERMAN ROAD
ROMEDEVILLE, IL 60446

IDOT is not a member of JULIE. If you are near any overhead lighting, intersection lighting or traffic signals, contact the IDOT Traffic Office at 815/284-5469 at least 48 hours prior to work.

NO STREAM PERMITS HAVE BEEN PROCURED FOR THIS PROJECT. NONE ARE REQUIRED FROM THE REGULATORY AGENCIES AS LONG AS THERE IS NO DEBRIS FALLING OR BEING PLACED INTO THE STREAM. ANY TEMPORARY FILL IN THE STREAM OR THE COMPROMISING OF THE DIKE (IF APPLICABLE) WILL NOT BE ALLOWED. IF THE CONTRACTOR CHOOSES TO USE ALTERNATE/MODIFIED CONSTRUCTION METHOD(S) FROM THE AFOREMENTIONED, THEY WILL BE RESPONSIBLE FOR OBTAINING THE PROPER PERMITS. NO RELIEF OR COMPENSATION WILL BE GIVEN FOR ANY DELAYS, WORKING DAYS CHARGED OR CALENDAR DAYS EXPIRED AS A RESULT OF THE LOSS OF TIME OR DELAY DURING THE RE-SUBMITTAL PROCESS TO PROCURE THE NECESSARY PERMIT(S) DUE TO THE CONTRACTOR CHOOSING ALTERNATE/MODIFIED CONSTRUCTION METHOD(S). ABSOLUTELY NO CONSTRUCTION ACTIVITIES WILL TAKE PLACE WITHOUT THE PROPER PERMITS BEING SECURED.

FILE NAME :	USER NAME : doesdd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS & STATE STANDARDS & GENERAL NOTES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
D:\BR\Draws\Whiteside\64J92 Repairs SN 098-0051 & SN 098-0052\CADD\207713-1\1-1.dwg	DRAWN	REVISED	5571			02 BRIDGE REPAIR 2014-2	WHITESIDE	33	2	
PLOT SCALE : 100.0000 / 1 in	CHECKED	REVISED	CONTRACT NO. 64J92							
Default	PLOT DATE : Fri Mar 28 11:06:45 2014	DATE	SCALE: _____			SHEET _____ OF _____ SHEETS	STA. _____ TO STA. _____	ILLINOIS FED. AID PROJECT		

△ Rev. 6-3-14