

# INDEX OF SHEETS

1	COVER SHEET
2	INDEX OF SHEETS & STATE STANDARDS & GENERAL NOTES
3	SUMMARY OF QUANTITIES
4	MAINTENANCE OF PEDESTRIAN TRAFFIC DETAILS
5 - 10	SUBSTRUCTURE REPAIR DETAILS SN 098-0051 & 098-0052
11	GENERAL PLAN AND ELEVATION SN 098-0051
12	JOINT REMOVAL & REPLACEMENT DETAILS AT ABUTMENTS SN 098-0051
13	PREFORMED JOINT STRIP SEAL AT ABUTMENTS SN 098-0051
14	FINGER PLATE REMOVAL & REPLACEMENT DETAILS AT PIER 3 SN 098-0051
15 - 16	FINGER PLATE JOINT DETAILS AT PIER 3 SN 098-0051
17	BAR SPLICER ASSEMBLY AND MECHANICAL SPLICER DETAILS SN 098-0051
18	GENERAL PLAN AND ELEVATION SN 098-0052
19	JOINT REMOVAL & REPLACEMENT DETAILS SN 098-0052
20	PREFORMED JOINT STRIP SEAL SN 098-0052
21	BAR SPLICER ASSEMBLY AND MECHANICAL SPLICER DETAILS SN 098-0052
22 - 32	EXISTING PLAN SHEETS FOR SN 098-0051 & 098-0052
33	TRAFFIC CONTROL FOR ROAD CLOSURE (DIST STD 40.1)

# STATE STANDARDS

701006 - 05	OFF-RD OPERATIONS, 2L, 2W, 15' (4.5 m) TO 24" (600 mm) FROM PAVEMENT EDGE
701201 - 04	LANE CLOSURE, 2L, 2W, DAY ONLY, FOR SPEEDS $\geq$ 45 MPH
701301 - 04	LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
701311 - 03	LANE CLOSURE 2L, 2W MOVING OPERATIONS - DAY ONLY
701801 - 05	SIDEWALK, CORNER OR CROSSWALK CLOSURE
701901 - 03	TRAFFIC CONTROL DEVICES
720011 - 01	SIGN PANEL MOUNTING DETAILS
728001 - 01	TELESCOPING STEEL SIGN SUPPORT
729001 - 01	APPLICATIONS OF TYPES A & B METAL POSTS (FOR SIGNS & MARKERS)

# GENERAL NOTES

All Borrow/Waste/Use sites must be approved by the Department prior to removing any material from the project or initiating any earthmoving activities, including temporary stockpiling outside the limits of construction.

The Contractor shall be responsible for protecting utility property during construction operations as outlined in Article 107.31 of the Standard Specifications. A minimum of 48 hours advance notice is required for non-emergency work. The JULIE number is 800-892-0123. The following listed utilities located within the project limits or immediately adjacent to the project construction limits are members of JULIE:

Electric: COMMONWEALTH EDISON COMPANY ATTN: NORA FERNANDEZ 123 ENERGY AVENUE ROCKFORD, IL 61109	CITY OF ROCK FALLS ATTN: DICK SIMON 1109 INDUSTRIAL PATK ROAD ROCK FALLS, IL 61071
---	---

Telephone: AT&T ATTN: DAVID CREEN 2800 7TH STREET MOLINE, IL 61265	US SPRINT ATTN: JAMES BURTON 5600 N RIVER ROAD/ ROSEMONT, IL 60018
--	---

Water: IL AMERICAN WATER COMPANY 304 SECOND AVENUE STERLING, IL 61081	CITY OF ROCK FALLS ATTN: TED PADILLA 603 WEST 10TH STREET ROCK FALLS, IL 610071
--	--

Sewer: CITY OF ROCK FALLS ATTN: EDWARD COX 603 WEST 10TH STREET ROCK FALLS, IL 61071	CITY OF STERLING ATTN: SCOTT SHUMARD 212 3RD AVENUE STERLING, IL 61081
--	---

Gas:  
NICOR GAS CO.  
ATTN: CONSTANCE LANE  
1844 FERRY ROAD  
NAPERVILLE, IL 60563

CATV:  
COMCAST CABLE  
ATTN: MICHAEL OWENS  
4450 KISHWAUKEE STREET  
ROCKFORD, IL 61109

Communications:  
G4S TECHNOLOGY, LLC  
1428 SHERMAN ROAD  
ROMEDEVILLE, IL 60446

IDOT is not a member of JULIE. If you are near any overhead lighting, intersection lighting or traffic signals, contact the IDOT Traffic Office at 815/284-5469 at least 48 hours prior to work.

NO STREAM PERMITS HAVE BEEN PROCURED FOR THIS PROJECT. NONE ARE REQUIRED FROM THE REGULATORY AGENCIES AS LONG AS THERE IS NO DEBRIS FALLING OR BEING PLACED INTO THE STREAM, ANY TEMPORARY FILL IN THE STREAM OR THE COMPROMISING OF THE DIKE (IF APPLICABLE) WILL NOT BE ALLOWED. IF THE CONTRACTOR CHOOSES TO USE ALTERNATE/MODIFIED CONSTRUCTION METHOD(S) FROM THE AFOREMENTIONED, THEY WILL BE RESPONSIBLE FOR OBTAINING THE PROPER PERMITS. NO RELIEF OR COMPENSATION WILL BE GIVEN FOR ANY DELAYS, WORKING DAYS CHARGED OR CALENDAR DAYS EXPIRED AS A RESULT OF THE LOSS OF TIME OR DELAY DURING THE RE-SUBMITTAL PROCESS TO PROCURE THE NECESSARY PERMIT(S) DUE TO THE CONTRACTOR CHOOSING ALTERNATE/MODIFIED CONSTRUCTION METHOD(S). ABSOLUTELY NO CONSTRUCTION ACTIVITIES WILL TAKE PLACE WITHOUT THE PROPER PERMITS BEING SECURED.

FILE NAME: D:\BR\Draws\Whiteside\64J92 Repair SN 098-0051 & SN 098-0052\CADD\0207713-sh1-00.dwg	USER NAME: djosidd	DESIGNED: _____	REVISED: _____	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>INDEX OF SHEETS &amp; STATE STANDARDS &amp; GENERAL NOTES</b>		F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLLOT SCALE: 100.0000' / 1" = 100'	CHECKED: _____	REVISED: _____	_____		5571	D2 BRIDGE REPAIR 2014-2	WHITESIDE	33	2		
PLLOT DATE: Fri Mar 28 11:00:45 2014	DATE: _____	REVISED: _____	_____		SCALE: _____ SHEET _____ OF _____ SHEETS STA. _____ TO STA. _____		CONTRACT NO. 64J92		ILLINOIS FED. AID PROJECT		
Default											