

IL 40 REPAIR SCHEDULE

LOCATION LOG MILES	LENGTH FT	MAINLINE		HMA SURF 2'' SQ YD	MIX FOR CRKS, JTS FLANGE TON	LEVEL BIND HM N50 TON	HMA SURF CSE MIX C N50 TONS	BIT MAT PRIME COAT POUND	RAISE REFL PAVT MARK REM EACH	PAINT PAVT MARK			SHORT TERM PAVT MARK FOOT	WORK ZONE PAVT MARK REM SQ FT
		WIDTH FT	AREA SQ YD							LINE 4''	LINE 6''	LINE 8''		
		2 APPLICATIONS								FOOT	FOOT	FOOT		
NORTHBOUND														
0.00 NORTH SIDE I-80 OVERPASS														
1.85 - 1.95	550	12.5	763.9	763.9	0.23	0.38	85.56	343.8	7	2200	280		55	18
3.05 - 3.25	1100	12.5	1527.8	1527.8	0.46	0.76	171.11	687.5	14	4400	560		110	37
3.50 - 3.70	1100	12.5	1527.8	1527.8	0.46	0.76	171.11	687.5	14	4400	560		110	37
4.00	30	12.5	41.7	41.7	0.01	0.02	4.67	18.8		120	20		3	1
4.60 - 5.00	2200	13	3177.8	3177.8	0.95	1.59	355.91	1430.0	28	8800	1100	520	220	73
6.20	30	12.5	41.7	41.7	0.01	0.02	4.67	18.8		120	20		3	1
7.70 - 8.10	2200	6	1466.7	1466.7	0.44	0.73	164.27	660.0		4400				
8.95 - 9.15	1100	12.5	1527.8	1527.8	0.46	0.76	171.11	687.5	14	4400	560		110	37
SOUTHBOUND														
0.00 IL 92 SOUTH CONST JT														
2.65 - 2.75	550	12.5	763.9	763.9	0.23	0.38	85.56	343.8	7	3300	280		55	18
2.90 - 3.10	1100	12.5	1527.8	1527.8	0.46	0.76	171.11	687.5	14	4400	560		110	37
6.10	30	12.5	41.7	41.7	0.01	0.02	4.67	18.8		120	20		3	1
7.10 - 7.50	2200	13	3177.8	3177.8	0.95	1.59	355.91	1430.0	28	8800	1100	520	220	73
8.40 - 8.60	1100	12.5	1527.8	1527.8	0.46	0.76	171.11	687.5	14	4400	560		110	37
8.80 - 9.00	1100	12.5	1527.8	1527.8	0.46	0.76	171.11	687.5	14	4400	560		110	37
9.40 - 9.60	1100	12.5	1527.8	1527.8	0.46	0.76	171.11	687.5	14	4400	560		110	37
9.95	30	12.5	41.7	41.7	0.01	0.02	4.67	18.8		120	20		3	1
TOTAL			20211.1	20211	6	10	2264	9095	165	58780	6760	1040	1332	444

•INTERMITTENT SPRING ROAD REPAIR 2014-1

FILE NAME =	USER NAME = duncanbd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
et:\pw\work\p1dot\duncanbd\0388072\0388086-sh1-schedule.dgn	DRAWN -	REVISED -	646			*	BUREAU	6	5	
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -	CONTRACT NO. 66D86							
PLOT DATE = 4/10/2014	DATE -	REVISED -	SCALE:			SHEET NO.	OF SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT