

RESURFACING SCHEDULE										
LOCATION				HMA SC	BIT	MIX CR JTS	LEV BIND	HMA SURF		
	LENGTH	WIDTH	AREA	"D" N50	MATLS	FLANGEWYS	HM N50	REM		
	FT	FT	SQ YD	TON	POUND	TON	TON	SQ YD		
LONG POINT RD. TO BNSF RAILWAY BRIDGE (LIVINGSTON COUNTY)										
RURAL										
NORTHBOUND LANE										
LM	TO	LM								
0.0			150.0	13	216.7	24.3	97.5	0.07	0.1	216.7
0.5	TO	0.6	300.0	13	433.3	48.5	195.0	0.13	0.2	433.3
2.1	TO	2.3	600.0	4	266.7	29.9	120.0	0.08	0.1	266.7
2.8			150.0	13	216.7	24.3	97.5	0.07	0.1	216.7
3.3	TO	3.9	2300.0	4	1022.2	114.5	460.0	0.31	0.5	1022.2
3.9	TO	4.0	300.0	13	433.3	48.5	195.0	0.13	0.2	433.3
4.5	TO	4.6	300.0	13	433.3	48.5	195.0	0.13	0.2	433.3
4.7	TO	4.8	300.0	13	433.3	48.5	195.0	0.13	0.2	433.3
5.4			150.0	13	216.7	24.3	97.5	0.07	0.1	216.7
SOUTHBOUND LANE										
LM	TO	LM								
0.4	TO	0.5	300.0	13	433.3	48.5	195.0	0.13	0.2	433.3
1.6			50.0	13	72.2	8.1	32.5	0.02	0.0	72.2
1.7	TO	1.8	300.0	13	433.3	48.5	195.0	0.13	0.2	433.3
2.1	TO	2.2	300.0	13	433.3	48.5	195.0	0.13	0.2	433.3
2.7	TO	2.8	300.0	13	433.3	48.5	195.0	0.13	0.2	433.3
3.4			75.0	13	108.3	12.1	48.8	0.03	0.1	108.3
3.9	TO	4.0	300.0	13	433.3	48.5	195.0	0.13	0.2	433.3
4.4	TO	4.6	300.0	13	433.3	48.5	195.0	0.13	0.2	433.3
RURAL SUBTOTAL					6453	723	2904	2.0	3.2	6453
URBAN										
NORTHBOUND LANE										
6.0	TO	6.3	900.0	13	1300.0	145.6	585.0	0.39	0.7	1300.0
SOUTHBOUND LANE										
6.0	TO	6.3	900.0	13	1300.0	145.6	585.0	0.39	0.7	1300.0
URBAN SUBTOTAL					2600	291	1170	0.8	1.3	2600
LIVINGSTON COUNTY SUBTOTAL					9053	1014	4074	2.8	4.5	9053
TOTAL					15474	1733	6964	4.7	7.7	15474

**AREA FROM LONG POINT RD. TO BNSF RAILWAY BRIDGE TO USE HMA SURFACE REMOVAL MILLINGS ON LOW SHOULDERS.