

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				100% STATE RURAL ROADWAY	100% STATE URBAN ROADWAY
				0005 KENDALL	0005 GRUNDY
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	6	2	4
40600535	LEVELING BINDER (HAND METHOD), N70	TON	10	4	6
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	923	923	
40603370	HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N90	TON	1377		1377
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SO FT	406		406
42400800	DETECTABLE WARNINGS	SO FT	60		60
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	20537	8244	12293
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	76		76
44000600	SIDEWALK REMOVAL	SO FT	406		406
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	76		76
67100100	MOBILIZATION	L SUM	1	0.4	0.6
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1		1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1		1

14

FILE NAME :	USER NAME : duncanbd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
os:\pw\work\p\p\p\p\duncanbd\0387041\036	090-shr-S00.dgn	DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	326	KEN-GRU	8	3
	PLOT SCALE * 100.0000 ' / 1" =	CHECKED -	REVISED -											
	PLOT DATE * 4/11/2014	DATE -	REVISED -											
											*INTERMITTENT SPRING ROAD REPAIR 2014-5 ILLINOIS FED. AID PROJECT			
											CONTRACT NO. 66090			