

CODE NO	ITEM	UNIT	CONSTRUCTION TYPE CODE	
			TOTAL QUANTITY	ROWY 0005 RURAL
40600400	MIXTURE FOR CRACKS, JOINTS AND FLANGEWAYS	TON	10	10
40600525	LEVELING BINDER (HAND METHOD), NS0	TON	27	27
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", NS0	TON	1238	1238
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", NT0	TON	2620	2620
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	34451	34451
67100100	MOBILIZATION	LSUM	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	LSUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	LSUM	1	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	6965	6965
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1834	1834
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	80817	80817
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	19087	19087
* 78009000	MODIFIED URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	566	566
* 78009004	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	6863	6863
* 78009006	MODIFIED URETHANE PAVEMENT MARKING - LINE 6"	FOOT	159	159
* 78009008	MODIFIED URETHANE PAVEMENT MARKING - LINE 8"	FOOT	762	762
* 78009012	MODIFIED URETHANE PAVEMENT MARKING - LINE 12"	FOOT	230	230
* 78009024	MODIFIED URETHANE PAVEMENT MARKING - LINE 24"	FOOT	322	322
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	45	45
78200300	PRISMATIC CURB REFLECTOR	EACH	16	16
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	813	813
X4060110	BITUMINOUS MATERIALS (PRIME COAT)	POUND	15503	15503

22

*Specialty Items

* INTERMITTENT SPRING ROAD REPAIR 2014-7

FILE NAME *	USER NAME * mcfaddenka	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\pwwork\mcfaddenka\d030793310	xxxxx-shr-schedule.dgn	DRAWN -	REVISED -						VAR		FORD	11	3
	PLOT SCALE * 1/8" = 1'-0"	CHECKED -	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO STA.	CONTRACT NO. 66092		
	PLOT DATE * 4/11/2014	DATE -	REVISED -		ILLINOIS REG. AID PROJECT								