EARTHWORK

	EARTHWORK		FOR INFORMATION ONLY				BORROW		TOPSOIL	
LOCATION STATION TO STATION	EXCAVATION (WIDENING)	EARTHWORK EXCAVATION	AVERAGE SHRINKAGE FACTOR	EARTH EXCAVATION (ADJUSTED)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) SHORTAGE (-)	SWELL FACTOR EXCAVATION		FURNISH AND PLACE, 4"	REMARKS
	CUYD	CU YD	%	CUYD	CU YD	CUYD	%	CU YD	SQ YD	
PRE-STAGE 1										
STA RT 797+50.00 TO 800+00.00	28		41.70%	11.81	0	12	0.18	14		
STA RT 802+40.00 TO 805+00.00	27		41.68%	11.35	0	11	0.18	13		
STA RT 803+50.00 TO 807+00.00		14	41.71%	5.76	6517	-6511	0.18	7683		
STA RT 804+00.00 TO 807+00.00									3605	
STAGE 1										
STA LT 794+50.00 TO 807+50.00		1164	75.50%	878.47	453	425	0.18	502	1479	* OMIT STA 800+00.00 TO 802+00.00
STAGE 2										
STA RT 794+50.00 TO 807+50.00		1334	76.09%	1014.69	1395	-380	1	380	2194	* OMIT STA 800+00.00 TO 802+00.00
PROJECT TOTAL	60	2515						8595	7280	

PAVEMENT MARKING

LOCATION STATION TO STATION	PAVE MARKING (FC	ORARY EMENT - LINE 24" DOT)	TEMPORARY PAVEMENT MARKING - LINE 4" (FOOT)		(FOOT)		RKING TAPE, YPE III 4" (FOOT) MODIFIED URE HANE PAVEMENT MARKING - LIN 4"		PAVEMENT MARKING - LINE 4"		ING - LINE RUMBLE STRIPS	
	WHITE	YELLOW	WHITE	YELLOW	WHITE	YELLOW	WHITE	YELLOW	EACH	FOOT		
STAGE 1												
STA RT 775+60.25									1			
STA RT 780+60.25									1			
STA RT 785+60.25									1			
STA LT 787+86.26									1			
STA LT 785+86.26									1			
STA LT 785+86.26									1			
STA RT 792+60.30	13											
STA RT 793+21.28 TO 808+37.30			1518									
STA RT 795+04.46 TO 806+52.09			1302									
STA LT 808+86.26	13											
STAGE 2												
STA 791+60.30 TO 808+88.47										164		
STA 792+60.30 TO 808+88.48							3258	408				
STA LT 793+34.60 TO 808+24.27					1496							
STA LT 794+92.50 TO 806+65.49					1173							
PROJECT TOTAL	26	0	2820	0	2669	0	3258	408	6	164		

<u>SEEDING</u>

		1					
LOCATION STATION TO STATION	SEEDING, CLASS 3	SEEDING, CLASS 7	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGRICULTURAL GROUND LIMESTONE	MULCH METHOD 2
	ACRE	ACRE	POUND	POUND	POUND	TON	ACRE
PRE-STAGE 1							
STA RT 794+79.35 TO 799+00.39		0.29					0.29
STA RT 802+68.86 TO 806+78.74		0.48					0.48
STA RT 803+68.86 TO 806+85.04		0.45					0.45
STAGE 1							
STA LT 794+26.61 TO 799+54.24	0.19	0.19	34.7	34.7	34.7	0.8	0.38
STA LT 802+13.08 TO 802+37.91	0.00	0.00	0.9	0.9	0.9	0.0	0.01
STA LT 802+41.82 TO 806+05.00	0.34	0.34	61.5	61.5	61.5	1.4	0.68
STA LT 804+03.19 TO 807 +19.02	0.17	0.17	30.2	30.2	30.2	0.7	0.34
STAGE 2							
STA RT 794+28.85 TO 799+88.96	0.33	0.33	59.8	59.8	59.8	1.3	0.66
STA RT 802+53.08 TO 802+67.30	0.00	0.00	0.2	0.2	0.2	0.0	0.002
STA RT 802+79.02 TO 806+05.00	0.33	0.33	58.8	58.8	58.8	1.3	0.65
STA RT 803+91.37 TO 807+19.02	0.17	0.17	30.7	30.7	30.7	0.7	0.34
PROJECT TOTAL	1.75	3.00	277	277	277	6.1	4.50

R.O.W. & SURVEY MARKERS

LOCATION	FURNISHING AND ERECTING R.O.W. MARKERS	PERMANENT SURVEY MARKERS, TYPE 1
	EACH	EACH
STAGE 2		
PLACED ON BRIDGE		1
STA 803+58.52	1	
STA 803+61.75	1	
STA 803+68.21	1	
STA 803+71.44	1	
STA 806+60.00	2	
STA 806+95.00	2	
PROJECT TOTAL	8	1

PAVEMENT MARKING REMOVAL

LOCATION STATION TO STATION	WORK ZONE PAVEMENT MARKING REMOVAL	PAVEMENT MARKING REMOVAL
	SQ FT	SQ FT
STAGE 1		
STA 792+60.44 TO 795+79.00		27
STA 805+79.08 TO 808+88.56		26
STAGE 2		
STA RT 792+60.30	26	
STA 793+34.60 TO 808+24.27	499	
STA 794+92.50 TO 806+65.49	391	
STA LT 808+86.26	26	
PROJECT TOTAL	942	53

DRAINAGE REMOVAL

LOCATION STATION TO STATION	CONCRETE HEADWALL REMOVAL	PIPE CULVERT REMOVAL		
	EACH	FOOT		
STAGE 1				
STA LT 798+70.48 TO 799+51.31		81		
STA LT 798+70.74	1			
STAGE 2				
STA LT 799+02.61	1			
STA LT 799+02.62 TO 799+78.68		77		
PROJECT TOTAL	2	158		

EROSION CONTROL

LOCATION STATION TO STATION	EROSION CONTROL BLANKET	HEAVY DUTY EROSION CONTROL BLANKET	TEMPORARY DITCH CHECKS	PERIMETER EROSION BARRIER	INLET & PIPE PROTECTION
	SQ YD	SQ YD	FOOT	FOOT	EACH
PRE-STAGE 1					
STA RT 794+26.61 TO 798+54.25				458.7	
STA LT 794+26.61 TO 798+54.25				353.0	
STA RT 800+6.82 TO 806+79.26				804.1	
STA LT 800+6.82 TO 806+79.26				673.4	
				5,5,1	
STAGE 1					
STA LT 794+26.61 TO 798+51.72				456.4	
STA LT 794+26.61 TO 796+59.82	188.6			400.4	
STA LT 796+60.83 TO 799+54.10	100.0	769.5			
STA LT 798+58.29 TO 798+64.80		700.0			1
STA LT 798+64.91 TO 799+78.75				116.5	<u>'</u>
STA LT 802+13.08 TO 802+37.00		23.5		110.5	
STA LT 802+41.00 TO 802+50.00		202.5			
STA LT 803+50.00 TO 806+06.00	1452.5	202.3			
STA LT 803+91.76 TO 804+08.42	1432.3	-	12		
STA LT 804+03.24 TO 805+50.00	229.0		12		
	229.0		12		
STA LT 804+41.64 TO 804+58.40					
STA LT 804+91.70 TO 805+08.37		500.0	12		
STA LT 805+50.53 TO 807+19.02		582.9			
STA LT 805+42.06 TO 805+58.37			12		
STA LT 805+55.71 TO 805+72.37			12		
STA LT 805+69.71 TO 805+86.37			12		
27, 27, 2					
STAGE 2	101.0				
STA RT 794+26.61 TO 796+59.82	401.3				
STA RT 796+59.82 TO 799+88.06		446.9			
STA RT 798+60.95 TO 798+67.34					1
STA RT 802+53.08 TO 802+67.65		4.1			
STA RT 802+79.05 TO 803+50.50		85.7			
STA RT 803+50.50 TO 806+05.00	1493.7				
STA RT 803+91.71 TO 804+08.01			12		
STA RT 803+90.79 TO 805+50.00	242.2				
STA RT 804+41.71 TO 804+58.37			12		
STA RT 804+91.71 TO 805+08.37			12		
STA RT 805+50.00 TO 807+19.02		583.2			
STA RT 805+42.01 TO 805+58.60			12		
STA RT 805+55.71 TO 805+72.38			12		
STA RT 805+69.71 TO 805+86.38			12		
PROJECT TOTAL	4007	2698	144	2862	2

PIPE CULVERTS

LOCATION STATION TO STATION	PIPE CULVERTS, CLASS D, TYPE 1 24"	PIPE CULVERTS, CLASS D, TYPE 2 24"	STEEL END SECTIONS 24"	FLAP GATE (SPECIAL)
	FOOT		EACH	EACH
STAGE 1				
STA LT 798+68.48 TO 799+53.34	85			
STA LT 798+68.35			1	
STA LT 798+52.98				1
STAGE 2				
STA RT 798+70.94 TO 799+80.75		110		
STA RT 798+70.35			1	
STA RT 799+80.83				1
PROJECT TOTAL	85	110	2	2

RAISED REFLECTIVE PAVEMENT MARKERS

LOCATION STATION TO STATION	RAISED REFLECTIVE PAVEMENT	RAISED REFLECTIVE PAVEMENT MARKER		
STATION TO STATION	MARKER REMOVAL	TWO-WAY AMBER		
	EACH	EACH		
STAGE 1				
STA 792+60.44 TO 795+79.00	4			
STA 805+79.08 TO 808+88.56	4			
STAGE 2				
STA 792+60.44 TO 808+88.56		8		
PROJECT TOTAL	8	8		

FILE NAME =	USER NAME = bemery	DESIGNED -	REVISED -	Γ
P:\Projects\2008 Projects\08379 IL 8 ov	er Kickapoo Creek\CV\CADD Sheets\D468697-sh	tDRAWNle.dgn-	REVISED -	i
	PLOT SCALE = 100.0000 '/ in.	CHECKED -	REVISED -	ĺ
	PLOT DATE = 3/20/2014	DATE -	REVISED -	ĺ

SCHEDULE	OF QUA	ANTITIES		F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEE NO.
IL 8 OVER KICKAPOO CREEK			1388	(Z-1D-BR-1)BR	PEORIA	89	16	
IL O OVER I	CIOICAI C	O OHEEK				CONTRACT	NO. 6	58697
TNO 2 OF 2 9	SHEFTS	STA	TO STA	EED DO	AD DICT NO THE INDIC EED AT	D DDO IECT		