SCHEDULE OF QUANTITIES

70300100 - SHORT TERM PAVEMENT MARKING - LINE 4" (MAINLINE)

C/L - SKIP-DASH

ROUTE	STATION	TO	STATION	TRAVEL DIRECTION	# OF LINES	LENGTH (FOOT)	70301000 WORK ZONE PVMNT MRK REM SQ. FT.
FAP 811	47+80	-	36+18	S.B.	1	290.5	96.7
FAP 811	47+80	-	40+98	N.B.	1	170.5	56.8
FAP 811	40+08	-	36+18	N.B.	1	97.5	32.5
FAP 811	35+40	-	22+23	S.B.	1	329.3	109.6
FAP 811	35+40	-	29+74	N.B.	1	141.5	47.1
FAP 811	28+83	-	22+23	N.B.	1	165.0	54.9
FAP 811	21+00	-	19+52	N.B.	1	37.0	12.3
FAP 811	20+84	-	18+63	S.B.	1	55.3	18.4
FAP 811	18+63	-	11+45.74	N.B. & S.B.	2	358.6	119.4
FAP 811	11+75.86	-	12+34	N.B. & S.B.	2	29.1	9.7
FAP 811	13+54	-	13+99	N.B.	1	11.3	3.7
				FAP 811 SUB-TOTAL =		1685.5	561.3

70300100 - SHORT TERM PAVEMENT MARKING - LINE 4" (MAINLINE)

SINGLE TURN LANE (EXIST. DOUBLE LINES)

ROUTE	STATION	TO	STATION	TRAVEL DIRECTION	# OF LINES	LENGTH (FOOT)	70301000 WORK ZONE PVMNT MRK REM SQ. FT.
FAP 811	37+16	-	36+18	N.B. & S.B.	1	9.8	3.3
FAP 811	24+24	-	22+23	N.B. & S.B.	1	20.1	6.7
FAP 811	20+84	-	19+52	N.B. & S.B.	1	13.2	4.4
FAP 811	12+89	-	11+45.74	N.B. & S.B.	2	28.7	9.5
FAP 811	11+75.86	-	12+34	N.B. & S.B.	2	11.6	3.9
FAP 811	13+54	-	13+99	N.B. & S.B.	1	4.5	1.5
				FAP 811 SUB-TOTAL =		87.9	29.3
				FAP 811 TOTAL =		3118.8	*
				FAP 811 USE =		3119.0	*

70300100 - SHORT TERM PAVEMENT MARKING - LINE 4" (MAINLINE)
TWO WAY LEFT TURN LANE

ROUTE	STATION	TO	STATION	TRAVEL DIRECTION	# OF LINES	LENGTH (FOOT)	70301000 WORK ZONE PVMNT MRK REM SQ. FT.
FAP 811	47+80	-	40+98	N.B. & S.B.	2	341.0	113.6
FAP 811	40+08	-	37+16	N.B. & S.B.	2	146.0	48.6
FAP 811	35+40	-	29+74	N.B. & S.B.	2	283.0	94.2
FAP 811	28+83	-	26+98.38	N.B. & S.B.	2	92.3	30.7
FAP 811	26+90.38	-	24+24	N.B. & S.B.	2	133.2	44.4
FAP 811	18+63	-	13+00	N.B. & S.B.	2	281.5	93.7
FAP 811	13+00	-	12+89	S.B.	1	2.8	0.9
				FAP 811 SUB-TOTAL =		1279.8	426.2

70300100 - SHORT TERM PAVEMENT MARKING - LINE 4" (MAINLINE)

SINGLE TURN LANE

ROUTE	STATION	TO	STATION	TRAVEL DIRECTION	# OF LINES	LENGTH (FOOT)	70301000 WORK ZONE PVMNT MRK REM SQ. FT.
FAP 811	36+96	-	36+18	N.B.	1	7.8	2.6
FAP 811	23+29	-	22+23	N.B.	1	10.6	3.5
FAP 811	20+84	-	19+52	N.B.	1	13.2	4.4
FAP 811	12+13	-	11+45.74	N.B.	2	13.5	4.5
FAP 811	11+75.86	-	12+34	N.B.	2	11.6	3.9
FAP 811	13+54	-	13+99	S.B.	2	9.0	3.0
				FAP 811 SUB-TOTAL =		65.7	21.9

70300210 TEMPORARY PAVEMENT MARKING - LETTERS & SYMBOLS (MAINLINE)

ROUTE	STATION	EACH	SQ. FT.	TYPE	70301000 WORK ZONE PVMNT MRK REM (SQ FT)
FAP 811	47+33	2	31.2	LEFT ARROW	31.2
FAP 811	45+40	2	31.2	LEFT ARROW	31.2
FAP 811	43+40	2	31.2	LEFT ARROW	31.2
FAP 811	41+40	2	31.2	LEFT ARROW	31.2
FAP 811	39+66	2	31.2	LEFT ARROW	31.2
FAP 811	37+58	2	31.2	LEFT ARROW	31.2
FAP 811	36+96	1	15.6	LEFT ARROW	15.6
FAP 811	36+38	1	15.6	LEFT ARROW	15.6
FAP 811	35+98	2	31.2	LEFT ARROW	31.2
FAP 811	33+37	2	31.2	LEFT ARROW	31.2
FAP 811	31+77	2	31.2	LEFT ARROW	31.2
FAP 811	30+16	2	31.2	LEFT ARROW	31.2
FAP 811	28+47	4	25.2	R.R.	25.2
FAP 811	28+47	2	108.0	R.R. "X"	108.0
FAP 811	28+41	2	31.2	LEFT ARROW	31.2
FAP 811	26+54	2	31.2	LEFT ARROW	31.2
FAP 811	25+81	4	25.2	R.R.	25.2
FAP 811	25+81	2	108.0	R.R. "X"	108.0
FAP 811	24+66	2	31.2	LEFT ARROW	31.2
FAP 811	23+29	1	15.6	LEFT ARROW	15.6
FAP 811	22+86	1	15.6	LEFT ARROW	15.6
FAP 811	22+43	1	15.6	LEFT ARROW	15.6
FAP 811	20+64	1	15.6	LEFT ARROW	15.6
FAP 811	20+08	1	15.6	LEFT ARROW	15.6
FAP 811	19+52	1	15.6	LEFT ARROW	15.6
FAP 811	18+21	2	31.2	LEFT ARROW	31.2
FAP 811	15+81	2	31.2	LEFT ARROW	31.2
FAP 811	13+42	2	31.2	LEFT ARROW	31.2
FAP 811	12+13	2	31.2	LEFT & RIGHT ARROW	31.2
FAP 811	11+61	2	31.2	LEFT & RIGHT ARROW	31.2
FAP 811	12+14	2	31.2	LEFT & RIGHT ARROW	31.2
FAP 811	13+74	2	41.6	LEFT & COMBO ARROW	41.6
		FAP 811 SUBTOTAL	1025.6		1025.6
		FAP 811 TOTAL =	1025.6		FAP 811 TOTAL = *
		FAP 811 USE =	1026.0		

* TOTAL WORK ZONE PAVEMENT MARKING REMOVAL COMES FROM ADDITIONAL PAY ITEMS.

FILE NAME =	USER NAME = evusuglob	DESIGNED BMC	REVISED -
c:\pw_work\pwidot\evusuglob\d0385126\D570A70-sht-schedule(Spring Const. Funds).dgn		DRAWN BMC	REVISED -
	PLOT SCALE = 40.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 4/3/2014	DATE 2-4-2011	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES - LOCATION #2 (MATTIS AVE.)

SCALE: N/A | SHEET NO. 2 OF 8 SHEETS | STA. - TO STA. -

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
811	D5 PATCH & RES 2014-2	CHAMPAIGN	45	24
		CONTRACT NO. 70A70		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		