

SCHEDULE OF QUANTITIES

70300280 - TEMPORARY PAVEMENT MARKING - LINE 24" (MAINLINE)

ROUTE	STATION	DESCRIPTION	LENGTH (FOOT)	70301000 WORK ZONE PVMNT MRK REM (SQ FT)
FAP 811	36+18	STOP BAR	33.3	66.6
FAP 811	35+40	STOP BAR	26.0	52.0
FAP 811	28+73	R.R. BAR	23.2	46.4
FAP 811	28+21	R.R. BAR	24.2	48.4
FAP 811	27+33	R.R. BAR	26.0	52.0
FAP 811	26+54	R.R. BAR	25.4	50.8
FAP 811	26+07	R.R. BAR	24.1	48.2
FAP 811	25+55	R.R. BAR	25.2	50.4
FAP 811	22+23	STOP BAR	48.2	96.4
FAP 811	20+84	STOP BAR	37.9	75.8
FAP 811	12+34	STOP BAR	48.8	97.6
FAP 811	13+54	STOP BAR	50.7	101.4
			393.0	786.0
FAP 811 TOTAL (24") =			393.0	*
FAP 811 PROJECT TOTAL =			6659.7	
FAP 811 PROJECT USE =			6660.0	

* TOTAL WORK ZONE PAVEMENT MARKING REMOVAL COMES FROM ADDITIONAL PAY ITEMS.

78003100 PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS & SYMBOLS (MAINLINE)

ROUTE	STATION	EACH	SQ. FT.	TYPE	X7830068 GRV RCSD PVT LT N SYM (SQ FT)
FAP 811	47+33	2	31.2	LEFT ARROW	98.3
FAP 811	45+40	2	31.2	LEFT ARROW	98.3
FAP 811	43+40	2	31.2	LEFT ARROW	98.3
FAP 811	41+40	2	31.2	LEFT ARROW	98.3
FAP 811	39+66	2	31.2	LEFT ARROW	98.3
FAP 811	37+58	2	31.2	LEFT ARROW	98.3
FAP 811	36+96	1	15.6	LEFT ARROW	49.2
FAP 811	36+38	1	15.6	LEFT ARROW	49.2
FAP 811	35+98	2	31.2	LEFT ARROW	98.3
FAP 811	33+37	2	31.2	LEFT ARROW	98.3
FAP 811	31+77	2	31.2	LEFT ARROW	98.3
FAP 811	30+16	2	31.2	LEFT ARROW	98.3
FAP 811	28+47	4	25.2	R.R.	-
FAP 811	28+47	2	108.0	R.R. "X"	324.7
FAP 811	28+41	2	31.2	LEFT ARROW	98.3
FAP 811	26+54	2	31.2	LEFT ARROW	98.3
FAP 811	25+81	4	25.2	R.R.	-
FAP 811	25+81	2	108.0	R.R. "X"	324.7
FAP 811	24+66	2	31.2	LEFT ARROW	98.3
FAP 811	23+29	1	15.6	LEFT ARROW	49.2
FAP 811	22+86	1	15.6	LEFT ARROW	49.2
FAP 811	22+43	1	15.6	LEFT ARROW	49.2
FAP 811	20+64	1	15.6	LEFT ARROW	49.2
FAP 811	20+08	1	15.6	LEFT ARROW	49.2
FAP 811	19+52	1	15.6	LEFT ARROW	49.2
FAP 811	18+21	2	31.2	LEFT ARROW	98.3
FAP 811	15+81	2	31.2	LEFT ARROW	98.3
FAP 811	13+42	2	31.2	LEFT ARROW	98.3
FAP 811	12+13	2	31.2	LEFT & RIGHT ARROW	98.3
FAP 811	11+61	2	31.2	LEFT & RIGHT ARROW	98.3
FAP 811	12+14	2	31.2	LEFT & RIGHT ARROW	98.3
FAP 811	13+74	2	41.6	LEFT & COMBO ARROW	140.9
FAP 811 SUB-TOTAL =			1025.6		3052.0
FAP 811 TOTAL =			1025.6		
FAP 811 USE =			1026.0		

78004210 PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 4"

						C/L - SKIP-DASH (WHITE)				
ROUTE	STATION	TO	STATION	TRAVEL DIRECTION	# OF LINES	LENGTH (FOOT)				
FAP 811	47+80	-	36+18	S.B.	1	290.5				
FAP 811	47+80	-	40+98	N.B.	1	170.5				
FAP 811	40+08	-	36+18	N.B.	1	97.5				
FAP 811	35+40	-	22+23	S.B.	1	329.3				
FAP 811	35+40	-	29+74	N.B.	1	141.5				
FAP 811	28+83	-	22+23	N.B.	1	165.0				
FAP 811	21+00	-	19+52	N.B.	1	37.0				
FAP 811	20+84	-	18+63	S.B.	1	55.3				
FAP 811	18+63	-	11+45.74	N.B. & S.B.	2	358.6				
FAP 811	11+75.86	-	12+34	N.B. & S.B.	2	29.1				
FAP 811	13+54	-	13+99	N.B.	1	11.3				
						1685.5	FAP 811 SUB-TOTAL =			

TWO WAY LEFT TURN LANE- SKIP-DASH (YELLOW)

ROUTE	STATION	TO	STATION	TRAVEL DIRECTION	# OF LINES	LENGTH (FOOT)				
FAP 811	47+80	-	40+98	N.B. & S.B.	2	341.0				
FAP 811	40+08	-	37+16	N.B. & S.B.	2	146.0				
FAP 811	35+40	-	29+74	N.B. & S.B.	2	283.0				
FAP 811	28+83	-	26+98.38	N.B. & S.B.	2	92.3				
FAP 811	26+90.38	-	24+24	N.B. & S.B.	2	133.2				
FAP 811	18+63	-	13+00	N.B. & S.B.	2	281.5				
FAP 811	13+00	-	12+89	S.B.	1	2.8				
						1279.8	FAP 811 SUB-TOTAL =			
						FAP 811 TOTAL (4") =		2965.2		
						FAP 811 USE (4") =		2966.0		

78009004 MODIFIED URETHANE PAVEMENT MARKING - LINE 4" (MAINLINE)

						TWO WAY LEFT TURN LANE- SOLID (YELLOW)					X7830070 GRV RCSD PVT MRKG 5"
ROUTE	STATION	TO	STATION	TRAVEL DIRECTION	# OF LINES	LENGTH (FOOT)	LENGTH (FOOT)				
FAP 811	47+80	-	40+98	N.B. & S.B.	2	1364.0	1364.0				
FAP 811	40+08	-	37+16	N.B. & S.B.	2	584.0	584.0				
FAP 811	35+40	-	29+74	N.B. & S.B.	2	1132.0	1132.0				
FAP 811	28+83	-	26+99.90	N.B. & S.B.	2	366.2	366.2				
FAP 811	26+88.85	-	24+24	N.B. & S.B.	2	529.7	529.7				
FAP 811	18+63	-	13+00	N.B. & S.B.	2	1126.0	1126.0				
FAP 811	13+00	-	12+89	S.B.	1	11.0	11.0				
						5112.9	5112.9	FAP 811 SUB-TOTAL =			
						FAP 811 SUB-TOTAL =		1279.8			1279.8
						FAP 811 SUB-TOTAL =		1279.8			1279.8

TWO WAY LEFT TURN LANE- SKIP-DASH (YELLOW)

						TWO WAY LEFT TURN LANE- SKIP-DASH (YELLOW)					X7830070 GRV RCSD PVT MRKG 5"
ROUTE	STATION	TO	STATION	TRAVEL DIRECTION	# OF LINES	LENGTH (FOOT)	LENGTH (FOOT)				
FAP 811	47+80	-	40+98	N.B. & S.B.	2	341.0	341.0				
FAP 811	40+08	-	37+16	N.B. & S.B.	2	146.0	146.0				
FAP 811	35+40	-	29+74	N.B. & S.B.	2	283.0	283.0				
FAP 811	28+83	-	26+98.38	N.B. & S.B.	2	92.3	92.3				
FAP 811	26+90.38	-	24+24	N.B. & S.B.	2	133.2	133.2				
FAP 811	18+63	-	13+00	N.B. & S.B.	2	281.5	281.5				
FAP 811	13+00	-	12+89	S.B.	1	2.8	2.8				
						1279.8	1279.8	FAP 811 SUB-TOTAL =			
						FAP 811 SUB-TOTAL =		1279.8			1279.8