

INDEX OF SHEETS

1. COVER
2. INDEX OF SHEETS, GENERAL NOTES, AND HIGHWAY STANDARDS
3. SUMMARY OF QUANTITIES
4. PLAN
5. TYPICAL SECTIONS
6. DETAILS

HIGHWAY STANDARDS

- 701001-02 OFF-RD OPERATIONS, 2L, 2W, MORE THAN 15' AWAY FROM EDGE OF PAVEMENT  
 701006-05 OFF-RD OPERATIONS, 2L, 2W, 15' TO 24" FROM EDGE OF PAVEMENT  
 701011-04 OFF-RD MOVING OPERATIONS, 2L, 2W, DAY ONLY  
 701901-03 TRAFFIC CONTROL DEVICES  
 B.L.R. 21-9 TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES FOR CONSTRUCTION ON RURAL HIGHWAYS  
 701301-04 LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS

GENERAL NOTES

1. ANY REFERENCE TO THE STANDARDS THROUGHOUT THE PLANS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE DEPARTMENT AS INCLUDED IN THE PLANS.
2. TRENCH BACKFILL UNDER THE ROADWAY WILL BE COURSE AGGREGATE.
3. REMOVAL OF EXISTING FIELD TILE WILL BE INCLUDED WITH THE STORM SEWER AND NOT PAID FOR SEPARATELY.

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS DISTRICT 6	
EXAMINED	March 31 20 14 <i>Michael P. ...</i> ENGINEER OF OPERATIONS
EXAMINED	MARCH 24 20 14 <i>Jimmy ...</i> ENGINEER OF PROJECT IMPLEMENTATION
EXAMINED	March 31 20 14 [Signature] ENGINEER OF PROGRAM DEVELOPMENT

FILE NAME *	USER NAME * shp-pld	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS, HIGHWAY STANDARDS AND GENERAL NOTES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\work\awidot\shp-pld\0358729\0672	43-ans-gennote.dgn	DRAWN -	REVISED -			612	(112) 1-3	SCHUYLER	6	2	
Default	PLOT SCALE * 2.0000 "/ in.	CHECKED -	REVISED -			SCALE:		SHEET OF SHEETS		STA. TO STA.	
	PLOT DATE * Apr-01-2014 06:06:30AM	DATE -	REVISED -			ILLINOIS FED. AID PROJECT CONTRACT NO. 72G43					