



PAY ITEM	UNIT	QUADRANT	
		SW	SE
SIDEWALK REMOVAL	SQ FT	86.0	155.0
CURB REMOVAL	FT	14.0	15.0
COMB. CONC. CURB & GUTTER REMOVAL	FT	8.0	19.0
COMB. CONC. CURB & GUTTER, TYPE B-6.24	FT	8.0	19.0
PCC SIDEWALK 4"	SQ FT	86.0	50.0
DETECTABLE WARNINGS	SQ FT	10.0	10.0

- NOTES:
1. SEE STANDARD 424006 FOR ADDITIONAL INFORMATION.
 2. REMOVAL LIMITS ARE TO EXISTING JOINTS.
 3. THE COST OF SIDE CURB SHALL BE INCLUDED IN PCC SIDEWALK 4".
 4. THE COST OF HOT-MIX ASPHALT REMOVAL AND PLACEMENT IN THE GUTTERS SHALL BE INCLUDED IN COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.24

DRAINAGE FLOW ARROW
 LANDING AREA - 4' X 4' MIN. 5' X 5' TYPICAL
 MAX 2.0%, 1.56% IS PREFERRED SLOPE IN ALL DIRECTIONS

FILE NAME =	USER NAME = steffenmk	DESIGNED -	REVISED -
ci:\pw\work\p\dot\steffenmk\d0187107\074475-sh\sidewalk-details.dgn		DRAWN -	REVISED -
Default	PLOT SCALE = 15.0000' / in.	CHECKED -	REVISED -
	PLOT DATE = 4/4/2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SIDEWALK DETAILS
LOST BRIDGE RD.

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
712	128RS-4,148KRS-2	Macon	73	40
CONTRACT NO. 74475				
ILLINOIS FED. AID PROJECT				