


PAY ITEM	UNIT	QUADRANT	
		SE	NE
SIDEWALK REMOVAL	SQ FT	156.0	169.0
CURB REMOVAL	FT		5.0
COMB. CONC. CURB & GUTTER REMOVAL	FT	16.0	16.0
COMB. CONC. CURB & GUTTER, TYPE B-6.24	FT	16.0	16.0
PCC SIDEWALK 4"	SQ FT	157.0	170.0
DETECTABLE WARNINGS	SQ FT	10.0	10.0

- NOTES:
- SEE STANDARD 424011 FOR ADDITIONAL INFORMATION.
 - REMOVAL LIMITS ARE TO EXISTING JOINTS.
 - THE COST OF SIDE CURB SHALL BE INCLUDED IN PCC SIDEWALK 4".



FILE NAME =	USER NAME = steffenmk	DESIGNED -	REVISED -
c:\pwork\pwork\stevfenmk\d0187107\074475-sh1-sidewalk-details.dgn		DRAWN -	REVISED -
Default	PLOT SCALE = 15.0000' / in.	CHECKED -	REVISED -
	PLOT DATE = 4/4/2014	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SIDEWALK DETAILS
EAST MAIN STREET**

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
712	128RS-4,148KRS-2	Macon	73	45
CONTRACT NO. 74475			ILLINOIS FED. AID PROJECT	