



US 36

US 36

PAY ITEM	UNIT	QUADRANT	
		SW	ISLAND
SIDEWALK REMOVAL	SQ FT	106.0	202.0
CURB REMOVAL	FT	14.0	
COMB. CONC. CURB & GUTTER REMOVAL	FT	6.0	11.0
COMB. CONC. CURB & GUTTER, TYPE B-6.24	FT	6.0	11.0
PCC SIDEWALK 4"	SQ FT	106.0	151.0
DETECTABLE WARNINGS	SQ FT	10.0	20.0

NOTES:

- SEE STANDARD 424001 FOR ADDITIONAL INFORMATION.
- REMOVAL LIMITS ARE TO EXISTING JOINTS.
- THE COST OF SIDE CURB SHALL BE INCLUDED IN PCC SIDEWALK 4".

→ DRAINAGE FLOW ARROW

LANDING AREA - 4' X 4' MIN. 5' X 5' TYPICAL
MAX 2.0%, 1.56% IS PREFERRED SLOPE IN ALL DIRECTIONS

FILE NAME =	USER NAME = steffenmk	DESIGNED -	REVISED -
ci:\pw\work\p\idot\steffenmk\d0187107\07	4475-shit-sidewalk-details.dgn	DRAWN -	REVISED -
Default	PLOT SCALE = 15.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 4/4/2014	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SIDEWALK DETAILS			
US 36			
SCALE:	SHEET	OF	SHEETS
	STA.		TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
712	128RS-4,148KRS-2	Macon	73	48
CONTRACT NO. 74475				
ILLINOIS FED. AID PROJECT				