ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 0005 80% FEDERAL 20% STATE	M23IL 0005 50% STATE 50% CITY	07COL 0005 100% CITY	07POL 0005 100% STATE	07AOL 0021 100% STATE		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1367	1367						
30300011	AGGREGATE SUBGRADE IMPROVEMENT	TON	2802	2802						
35501328	HOT-MIX ASPHALT BASE COURSE, 11"	SQ YD	4134	4134						
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	1420	1420						
~~40600100~~	~~BITUMINOUS MATERIALS (PRIME COAT)~~	~~GALLON~~	~~2659~~	~~2366~~	~~58~~	~~235~~				
40600300	AGGREGATE (PRIME COAT)	TON	53	47	1	5				
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	1118	994	25	99				
40600990	TEMPORARY RAMP	SQ YD	133	133						
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	2234	1987	50	197				
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	5175	3161		2014				
42400800	DETECTABLE WARNINGS	SQ FT	636	368		268				
44000100	PAVEMENT REMOVAL	SQ YD	4101	4101						
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	26586	23657		2929				
44000300	CURB REMOVAL	FOOT	3	1.4		1.6				