SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 100% STATE 0005		
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	8	8		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	400	400		
40600990	TEMPORARY RAMP	SQ YD	68	68		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1581	1581		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	37	37		
44201785	CLASS D PATCHES, TYPE I, 12 INCH	SQ YD	60	60		
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	1118	1118		
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	124	124		
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	130	130		
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	310	310		
67100100	MOBILIZATION	L SUM	1	1		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
70300100	SHORT TERM PAVEMENT MARKING	FOOT	1128	1128		
13						

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 100% STATE 0005		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	115	115		
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	13750	13750		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	73	73		
X4060110	BITUMINOUS MATERIALS (PRIME COAT)	POUND	8471	8471		
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	18424	18424		
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	28	28		
Z0049799	PROTECTING OR RESETTING SURVEY MARKERS	EACH	7	7		
Z0070202	SURVEY MARKER VAULT	EACH	7	7		
8						

* SPECIALTY ITEM

FILE NAME =	USER NAME = steffenmk	DESIGNED -	REVISED -
c:\pw_work\pwidot\steffenmk\d0364918\D774670-sht-soq.dgn		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
Default	PLOT DATE = 4/1/2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N/A | SHEET 1 OF 1 SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
320	D7 HMA RESURF 2015-4	MOULTRIE	17	3

CONTRACT NO. 74670

ILLINOIS FED. AID PROJECT