

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			80/20 FED/ST	80/20 FED/ST	80/20 FED/ST
				0014	0040	0043			
				BRIDGE REHAB	SIGN STRUCTURES	UTILITIES			
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	300	300					
28100813	STONE DUMPED RIPRAP, CLASS A7	TON	35,085	35,085					
50102400	CONCRETE REMOVAL	CU. YD.	109.1	105.8	3.3				
50157300	PROTECTIVE SHIELD	SQ. YD.	617	617					
50300100	FLOOR DRAINS	EACH	100	100					
50300255	CONCRETE SUPERSTRUCTURE	CU. YD.	110	105.2	4.8				
50300260	BRIDGE DECK GROOVING	SQ. YD.	3,058	3,058					
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L. SUM	1	1					
50500505	STUD SHEAR CONNECTIONS	EACH	19,740	19,740					
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	20,850	19,820	1,030				
50800530	MECHANICAL SPLICERS	EACH	6		6				
52000110	PREFORMED JOINT STRIP SEAL	FOOT	504	504					
52000600	FABRIC REINFORCED ELASTOMERIC TROUGH	FOOT	214	214					
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE 1	EACH	35	35					



USER NAME - #USER#	DESIGNED - JAH	REVISED -
PLOT SCALE - #SCALE#	DRAWN - JAH	REVISED -
PLOT DATE - #DATE#	CHECKED - GRE	REVISED -
	DATE - 2/2014	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES			
MLK BRIDGE OVER MISSISSIPPI RIVER			
SCALE: N.T.S.	SHEET NO. 1 OF 4 SHEETS	STA.	TO STA.

F.A.P. RATE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
799	18A, DRS-2	ST. CLAIR	156	3
ILLINOIS FED. AID PROJECT			CONTRACT NO. 76803	