



**SECTION THRU BARREL**  
(Stations along CL Roadway)

**GENERAL NOTES**

Work shown in this detail shall be performed in accordance with applicable portions of sections 207 and 540 of the Standard Specifications.

Porous Granular Material shall extend 2 feet beyond the outside shoulder.

This work shall be paid for at the contract unit price per cubic yard for Granular Backfill for Structures.

Excavation for the proposed Box Culvert and Box Culvert End Sections shall be considered included in the pay item "Precast Concrete Box Culverts 5' x 5'".

ITEM	UNIT	TOTAL
Granular Backfill for Structures	Cu. Yd.	166

X:\CH\1E\2011\11004-17\CAD\Plans\060-2490\_Culvert.dgn



USER NAME =	DESIGNED -	REVISED -
	CHECKED -	REVISED -
PLOT SCALE =	DRAWN -	REVISED -
PLOT DATE =	CHECKED -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**DETAILS - GRANULAR BACKFIL**  
**STA. 734 + 80.00 CULVERT REPLACEMENT - S.N. 060-2490**

SHEET NO. 6 OF 8 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
785	(133,134,135)RS-4	MADISON	28	26
			CONTRACT NO. 76058	
ILLINOIS FED. AID PROJECT				