

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0005		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	275	275		
70600250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2		
70600350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2		
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	198	198		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	113857	113857		
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	629	629		
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	84	84		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	575	575		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	575	575		
* 80300100	LOCATING UNDERGROUND CABLE	FOOT	40	40		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0005		
88600600	DETECTOR LOOP REPLACEMENT	FOOT	909	909		
X5860110	GRANULAR BACKFILL FOR STRUCTURES	CU YD	300	300		
Z0038115	PORTLAND CEMENT CONCRETE SURFACE REMOVAL 1/2"	SQ YD	4813	4813		
Z0073002	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	400	400		
4						
Ø Z0076600	TRAINEES	HOURL	500	500		
Ø Z0076604	TRAINEES TRAINING PROGRAM GRADUATE	HOURL	500	500		

* SPECIALTY ITEM

Ø 0042

FILE NAME *	USER NAME * burnsideam	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
o:\pr_work\p\p\d\burnsideam\08351326\078558-akt-plan.dgn		DRAWN -	REVISED -			785	(133,134,135)RS-4	MADISON	28	5
PLOT SCALE * 100.0000' / 1" =		CHECKED -	REVISED -		SCALE:					
PLOT DATE * 3/28/2014		DATE -	REVISED -		SHEET OF SHEETS	STA.	TO STA.			
										ILLINOIS FED. AID PROJECT

CONTRACT NO. 76G58