

RESURFACING SCHEDULE							
LOCATION			LENGTH (FOOT)	WIDTH (FOOT)	HMA SURFACE REMOVAL 2"	BITUMINOUS MATERIAL (PRIME COAT)	POLY-HMA SURF CRSE, MIX E, N90, 2"
STA.	TO	STA.					
NORTHBOUND							
1373+06	TO	1765+71	39265	12	52354	23559	5864
1767+78	TO	1873+88	10610	12	14146	6366	1584
TOTAL:					66500	29925	7448

PAVEMENT MARKING SCHEDULE												
STATION TO STATION	DIR	LENGTH	SHORT TERM PAVEMENT MARKING	TEMPORARY PAVEMENT MARKING		RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	RAISED REFLECTIVE PAVEMENT MARKERS	PAINT PAVEMENT MARKING	PREFORMED PLASTIC PAVEMENT MARKING, TY. B INLAID	WORK ZONE PAVEMENT MARKING REMOVAL		
				6" SOLID YELLOW	6" SKIP-DASH WHITE						FOOT	FOOT
		FOOT	FOOT	FOOT	FOOT	EACH	EACH	FOOT	FOOT	SQ FT		
MAINLINE												
1373+06	TO	1765+71	NB	39265	10994	39265	9816	982	982	39265	9816	27289
1767+78	TO	1873+88	NB	10610	2971	10610	2653	265	265	10610	2653	7374
SUBTOTAL				13965	49875	12469	1247	1247	49875	12469		
TOTAL				13965	62344	1247	1247	49875	12469	34663		

TEMPORARY RAMP SCHEDULE				
DIR	STATION	LTH	WTH	AREA
		FT	FT	SQ YD
MAINLINE				
NB	1373+06.00	7	12	9
NB	1765+71.22	7	12	9
NB	1767+78.20	7	12	9
NB	1873+88.00	7	12	9
TOTAL				36