SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 0021 90% FED 10% STATE 0021		
X0325086	CONDUIT ATTACHED TO STRUCTURE, 4" DIA.,	FOOT	120	120		
	FIBERGLASS BULLET RESISTANT, MULTI-DUCT					
X0325482	REMOVE EXISTING ITS EQUIPMENT	EACH	5	5		
X0325483	SFP-GE-L SFP MODULE	EACH	10	10		
X0325484	SFP-GE-Z SFP MODULE	EACH	2	2		
X0326912	3000 LAYER 2 SWITCH	EACH	5	5		
X8102839	UNDERGROUND CONDUIT, PVC, 4"	FOOT	21507	21507		
	DIA., MULTI-DUCT					
X8110128	CONDUIT ATTACHED TO STRUCTURE, 4" DIA.,	FOOT	546	546		
	PVC TYPE C					
X8710075	FIBER OPTIC CABLE IN CONDUIT, 72 COND.	FOOT	25283	25283		
	S.M. F.O.					

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 0021		

FILE NAME =	USER NAME = prestonme	DESIGNED -	REVISED -
c:\pw_work\pwidot\prestonme\d0355968\d76g95-sht-ITS.dgn		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 3/20/2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ITS SUMMARY OF QUANTITIES
2 OF 2

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
270	DIST 8 ITS 2014-2	MADISON	37	4
		CONTRACT NO. 76G95		

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT