

SUMMARY OF QUANTITIES

100% STATE

100% STATE

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0005		
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	747	747		
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	22	22		
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	22	22		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	40.3	40.3		
40600300	AGGREGATE (PRIME COAT)	TON	193	193		
40600990	TEMPORARY RAMP	SQ YD	163	163		
40603087	HOT-MIX ASPHALT BINDER COURSE, IL-19.0 FG, N70	TON	2863	2863		
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	16199	16199		
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	63	63		
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	119338	119338		
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	7	7		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	690	690		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0005		
44004250	PAVED SHOULDER REMOVAL	SQ YD	510	510		
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	710	710		
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	512	512		
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	680	680		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4		
67100100	MOBILIZATION	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1		
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	15	15		
70300100	SHORT TERM PAVEMENT MARKING	FOOT	9642	9642		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	314562	314562		