GENERAL NOTES

PEAK HOUR RESTRICTIONS ON IL 15																								
	12:00 AM	1:00 AM	2:00 AM	3:00 AM	4:00 AM	5:00 AM	6:00 AM	7:00 AM	8:00 AM	9:00 AM	10:00 AM	11:00 AM	12:00 PM	1:00 PM	2:00 PM	3:00 PM	4:00 PM	5:00 PM	6:00 PM	7:00 PM	8:00 PM	9:00 PM	10:00 PM	11:00 PM	12:00 AM
WESTBOUND IL 15 FROM 0.4 MILES WEST OF IL 163 TO IL 163	1 LANE CLOSURE ALLOWED						NO LANE CLOSURES ALLOWED			1 LANE CLOSURE ALLOWED														
EASTBOUND IL 15 FROM 0.4 MILES WEST OF IL 163 TO IL 163	1 LANE CLOSURE ALLOWED															NO LANE CLOSURES ALLOWED			1 LANE CLOSURE ALLOWED						
WESTBOUND IL 15 FROM IL 163 TO 0.4 MILES EAST OF I-255	2 LANE CLOSURES ALLOWED						NO LANE CLOSURES ALLOWED			2 LANE CLOSURES ALLOWED						1 LANE CLOSURE ALLOWED			2 LANE CLOSURES ALLOWED						
EASTBOUND IL 15 FROM IL 163 TO 0.4 MILES EAST OF I-255	2 LANE CLOSURES ALLOWED							1 LANE CLOSURE ALLOWED		2 LANE CLOSURES ALLOWED						NO LANE CLOSURES ALLOWED			2 LANE CLOSURES ALLOWED						

MIXTURE REQUIREMENTS

ROUTE	FAP 674(IL-158)
SECTION	29-I-1, (31, 410, 410-1) I-1
COUNTY	ST. CLAIR
CONTRACT	76H25

DESCRIPTION:	PATCHING IL-158 FROM US 50 TO IL 161

	IL-158
ADT (Construction Yr.)	19600
MU%:	2.3
SU%:	4.3
20 YR. ESAL:	3.64

MIXTURE USE	PATCHING	PATCHING
AC/PG	PG-64-22	PG-64-22
RAP % (MAX)	SEE SPEC	SEE SPEC
DESIGN AIR VOIDS	4.0% @ Ndes=90	4.0% @ Ndes=90
MIX COMPOSITION		
(GRADATION MIXTURE)	IL 19.0 FG	IL 9.5
FRICTION AGG	MIXTURE "B"	MIXTURE "D"
QUALITY MGMT PROGRAM	QC/QA	QC/QA

* FAP 103/674