

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				URBAN	
				100% STATE	
				ROADWAY	0005
		URBAN			
44200549	CLASS A PATCHES, TYPE I, 10 INCH	SO YD	428	428	
44200553	CLASS A PATCHES, TYPE II, 10 INCH	SO YD	1736	1736	
44200557	CLASS A PATCHES, TYPE III, 10 INCH	SO YD	241	241	
44200559	CLASS A PATCHES, TYPE IV, 10 INCH	SO YD	623	623	
44213000	PATCHING REINFORCEMENT	SO YD	3026	3026	
44213200	SAW CUTS	FOOT	13403	13403	
44213204	TIE BARS 3/4"	EACH	381	381	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3	
67100100	MOBILIZATION	L SUM	1	1	
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	42	42	
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1	
<b>70100815</b>	<b>TRAFFIC CONTROL AND PROTECTION, STANDARD 701440</b>	L SUM	1	1	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	9	9	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	540	540	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2605	2605	

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				URBAN	
				100% STATE	
				ROADWAY	0005
		URBAN			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	179	179	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2605	2605	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	82	82	
x7010410	SPEED DISPLAY TRAILER	CAL MO	3	3	
φ 20076604	TRAINEES TRAINING PROGRAM GRADUATE	HOUR	500	500	
20076600	TRAINEES	HOUR	0		



\* SPECIALTY ITEM

△ REVISED 6-2-14

FILE NAME =	USER NAME = wadmara_jb	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ar\pwwork\pwwork\wadmara_jb\48368757\0675126-sh1-plan.dgn	DRAWN -	REVISED -	255			DIST. 8 PATCHING 2014-2	VARIOUS	8	3	
PLOT SCALE = 1/80.0000' / 1"	CHECKED -	REVISED -	CONTRACT NO. 76H26							
PLOT DATE = 4/11/2014	DATE -	REVISED -	ILLINOIS FED. AID PROJECT							
				SCALE:	SHEET OF SHEETS	STA. TO STA.				