

SUMMARY OF QUANTITIES

FAS 960 (US 45)
RURAL
80% FED.; 20% STATE
RESURFACING
MASSAC COUNTY
CONSTRUCTION TYPE
CODE 0005

CODE NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY
40600647	LEVELING BINDER (MACHINE METHOD), IL-9.5FG, N90	TON	6595
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	843
40600990	TEMPORARY RAMP	SQ YD	90
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	13254
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	509
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	143778
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	13268
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	735
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	480
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	820
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1971
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	5
67100100	MOBILIZATION	L SUM	1

13

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
es:\pwork\pwork\hollie\0269923\7829	teht-plan.dgn	DRAWN -	REVISED -		960	39RS-8, 40RS-10, 41RS-6	Massac	38	5				
	PLOT SCALE = 1/8" = 100.0000' / in.	CHECKED -	REVISED -		CONTRACT NO. 78219				ILLINOIS FED. AID PROJECT				
	PLOT DATE = 3/29/2014	DATE -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.			