

INDEX OF SHEETS

- 1 COVER SHEET
- 2 GENERAL NOTES, INDEX OF SHEETS, AND STANDARDS
- 3 SUMMARY OF QUANTITIES
- 4 GENERAL PLAN AND ELEVATION SN 041-0070 & 041-0071
- 5 STAGING DETAILS
- 6 JOINT REPLACEMENT AND REINFORCEMENT DETAILS SN 041-0070 WEST ABUTMENT & SN 041-0071 EAST ABUTMENT
- 7 JOINT REPLACEMENT AND REINFORCEMENT DETAILS SN 041-0070 EAST ABUTMENT & SN 041-0071 WEST ABUTMENT
- 8 BACKWALL REPAIR, RAIL POST, AND DRAIN EXTENSION DETAILS
- 9 BAR SPLICER ASSEMBLY DETAILS
- 10 PREFORMED JOINT STRIP SEAL DETAILS
- 11 TEMPORARY CONCRETE BARRIER FOR STAGE CONSTRUCTION
- 12 WIDE LOAD SIGNING PLAN

GENERAL NOTES

- 1) AT ALL LOCATIONS WHERE PROPOSED CONCRETE PAVEMENT JOINS AN EXISTING HOT-MIX ASPHALT OR CONCRETE PAVEMENT, A FULL DEPTH SAWED JOINT SHALL BE CONSTRUCTED. THE COST OF THIS JOINT WILL BE INCLUDED IN THE COST OF THE TYPE OF PAVEMENT BEING CONSTRUCTED.
- 2) IN ADDITION TO THE REQUIREMENTS OF ARTICLE 107.16 THE CONTRACTOR SHALL PROTECT THE SURFACE OF ALL BRIDGE DECKS AND BRIDGE APPROACH PAVEMENTS IN A MANNER SATISFACTORY TO THE ENGINEER BEFORE ANY EQUIPMENT IS ALLOWED TO CROSS THE STRUCTURE. PROTECTION SHALL BE PROVIDED FOR ALL EQUIPMENT AS DEFINED IN ARTICLE 101.16 REGARDLESS IF TRACK MOUNTED OR WHEELED.
- 3) ANY TIME THE CONCRETE BARRIER IS NOT IN THE PROPER POSITION, FLAGGERS SHALL BE IN PLACE TO CONTROL TRAFFIC.
- 4) PATCHING QUANTITIES ARE FOR ESTIMATED. THE FINAL LOCATIONS AND QUANTITIES WILL BE DETERMINED BY THE ENGINEER.
- 5) COMMITMENTS: NONE AS OF MARCH 21, 2014.

STANDARDS

- 000001-06 STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
- 001001-02 AREAS OF REINFORCEMENT BARS
- 001006 DECIMAL OF AN INCH AND OF A FOOT
- 643001-02 SAND MODULE IMPACT ATTENUATORS
- 701101-04 OFF-RD OPERATIONS, MULTILANE, 15' TO 24" FROM PAVEMENT EDGE
- 701106-02 OFF-RD OPERATIONS, MULTILANE, MORE THAN 15' AWAY
- 701400-07 APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
- 701402-09 LANE CLOSURE, FREEWAY/EXPRESSWAY, WITH BARRIER
- 701426-06 LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPER., FOR SPEEDS > 45 MPH
- 701901-03 TRAFFIC CONTROL DEVICES
- 704001-07 TEMPORARY CONCRETE BARRIER

Prepared By:	<i>Joe Markewicz</i> DISTRICT STUDIES & PLANS ENGINEER
Examined By:	<i>[Signature]</i> DISTRICT LAND ACQUISITION ENGINEER
Examined By:	<i>[Signature]</i> DISTRICT PROGRAM DEVELOPMENT ENGINEER
Examined By:	<i>[Signature]</i> DISTRICT OPERATIONS ENGINEER
Examined By:	<i>[Signature]</i> DISTRICT PROJECT IMPLEMENTATION ENGINEER
Examined By:	<i>[Signature]</i> DISTRICT CONSTRUCTION ENGINEER
Examined By:	<i>[Signature]</i> DISTRICT MATERIALS ENGINEER

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

GENERAL NOTES, INDEX OF SHEETS, AND STANDARDS

FILE NAME *	USER NAME * adomson	DESIGNED - _____	REVISED - _____
ci\pwork\widot\adomson\08379162\7837	sh-t-plan.dgn	DRAWN - _____	REVISED - _____
#MODELNAME#	PLOT SCALE * 100.0000' / 1" =	CHECKED - _____	REVISED - _____
	PLOT DATE * 3/25/2014	DATE - _____	REVISED - _____

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	*	JEFFERSON	12	2
CONTRACT NO. 78371				
ILLINOIS FED. AID PROJECT				

SCALE: _____ SHEET _____ OF _____ SHEETS STA. _____ TO STA. _____