CLASS D PATCHING (FOR INFORMATION ONLY)

SOUTHBOUND LANE

STATION / LOCATION							CLASS D PATCHING, TY I 9 INCHES	CLASS D PATCHING, TY II 9 INCHES	CLASS D PATCHING, TY I 13 INCHES	CLASS D PATCHING, TY II 13 INCHES	CLASS D PATCHING, TY III 13 INCHES	CLASS D PATCHING, TY I 14 INCHES	CLASS D PATCHING, TY II 14 INCHES	CLASS D PATCHING, TY III 14 INCHES	CLASS D PATCHING, TY IV 14 INCHES	CLASS D PATCHING, TY I 15 INCHES	CLASS D PATCHING, TY II 15 INCHES	CLASS D PATCHING, TY III 15 INCHES	CLASS D PATCHING, TY IV 15 INCHES	CLASS D PATCHING, TY II 17 INCHES
LANE	STATION	MILEPOST	LENGTH (FT)	WIDTH (FT)	AREA (YD^2)	TOTAL AREA (YD^2)	(YD^2)	(YD^2)	(YD^2)	(YD^2)	(YD^2)	(YD^2)	(YD^2)	(YD^2)	(YD^2)	(YD^2)	(YD^2)	(YD^2)	(YD^2)	(YD^2)
SB	525+25	6.27	5	11.5	6.39	6.39				6.39										
SB	525+75	6.26	4	11.5	5.11	5.11				5.11										
SB	526+55	6.25	5	11.5	6.39	6.39				6.39										
SB	526+85	6.24	5	11.5	6.39	6.39				6.39										
SB	527+75	6.23	4	11.5	5.11	5.11				5.11										
SB	529+00	6.20	4	11.5	5.11	5.11				5.11										
SB	549+95	5.81	4	11.5	5.11	5.11				5.11										
SB	552+15	5.76	4	11.5	5.11	5.11				5.11										
SB	553+25	5.74	6	11.5	7.67	7.67				7.67										
SB	554+75	5.71	15	11.5	19.17	19.17					19.17									
SB	556+25	5.69	4	11.5	5.11	5.11				5.11										
SB	560+25	5.61	4	11.5	5.11	5.11				5.11										
SB	560+65	5.60	4	11.5	5.11	5.11				5.11										
SB	562+35	5.57	7	11.5	8.94	8.94				8.94										
SB	722+45	2.54	4	11	4.89	4.89						4.89								
SB	726+25	2.47	4	11	4.89	4.89						4.89								
SB	727+20	2.45	4	11	4.89	4.89						4.89								
SB	728+00	2.43	4	11	4.89	4.89										4.89				
SB	728+50	2.42	4	11	4.89	4.89										4.89				
SB	729+10	2.41	4	11	4.89	4.89										4.89				
SB	729+80	2.40	4	11	4.89	4.89										4.89				
SB	732+50	2.35	4	11	4.89	4.89										4.89				
SB	732+90	2.34	4	11	4.89	4.89										4.89				
SB	733+50	2.33	4	11	4.89	4.89										4.89				
SB	734+10	2.32	12	11	14.67	14.67											14.67			
SB	778+31	1.49	10	11	12.22	12.22											12.22			
SB	785+47	1.35	4	11	4.89	4.89						4.89								
SB	787+17	1.32	5	11	6.11	6.11							6.11							
SB	787+90	1.30	4	11	4.89	4.89						4.89								
SB	788+30	1.30	12	11	14.67	14.67							14.67							
SOUTHBOUND SUBTOTAL 4										76.67	19.17	24.44	20.78			34.22	26.89			
SOUTHBOUND SUBTOTAL 3												2.67	170.94	50.56	25.56					
SOUTHBOUND SUBTOTAL 2									2.67	38.17	17.89		126.17		36.11		5.11	16.67	213.33	10.22
SOUTHBOUND SUBTOTAL 1									2.67	87.00		4.67	102.17	16.67						