

## SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	FRANKLIN COUNTY	
				ROADWAY	RURAL
CONSTRUCTION TYPE CODE				100% STATE	
				0005	
X4060110	BITUMINOUS MATERIALS (PRIME COAT)	POUND	11285	11285	
Z0034105	MATERIAL TRANSFER DEVICE	TON	3155	3155	
35101400	AGGREGATE BASE COURSE, TYPE B	TON	23	23	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	3	3	
40600647	LEVELING BINDER (MACHINE METHOD), IL-9.5 FC, N90	TON	1,048	1,048	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	419	419	
40600990	TEMPORARY RAMP	SQ YD	130	130	
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	2,107	2,107	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	24	24	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	23,420	23,420	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	1,398	1,398	
44200144	PAVEMENT PATCHING, TYPE II, 12"	SQ YD	1,001	1,001	
44200148	PAVEMENT PATCHING, TYPE III, 12"	SQ YD	297	297	
44200150	PAVEMENT PATCHING, TYPE IV, 12"	SQ YD	185	185	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	429	429	
67100100	MOBILIZATION	L SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2	2	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1,736	1,736	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	20,652	20,652	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	6,684	6,684	
* 78001110	PAVEMENT PAINT MARKING - LINE 4"	FOOT	20,652	20,652	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	109	109	

\* SPECIALTY ITEM

FILE NAME *	USER NAME * Stoverda	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
***-CADB.dgn		DRAWN -	REVISED -			869	10IRS-6	FRANKLIN	13	5
PLOT SCALE - 5000:1		CHECKED -	REVISED -			CONTRACT NO. 78388				
PLOT DATE - 3/26/2014		DATE -	REVISED -			ILLINOIS FED. AID PROJECT				