

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				80% FED	20% STATE
			URBAN		
			ROADWAY		
			0005		
X4420726	CLASS C PATCHES, TYPE II, 10 INCH (SPECIAL)	SO YD	11		11
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GALLON	978		978
40600300	AGGREGATE (PRIME COAT)	TON	16		16
40600990	TEMPORARY RAMP	SO YD	50		50
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	1217		1217
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	10862		10862
44201349	CLASS C PATCHES, TYPE I, 10 INCH	SO YD	20		20
44201353	CLASS C PATCHES, TYPE II, 10 INCH	SO YD	375		375
44201357	CLASS C PATCHES, TYPE III, 10 INCH	SO YD	140		140
44201359	CLASS C PATCHES, TYPE IV, 10 INCH	SO YD	332		332
67100100	MOBILIZATION	L SUM	1		1
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1		1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1		1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2		2
70300100	SHORT TERM PAVEMENT MARKING	FOOT	928		928

15

FILE NAME -	USER NAME - #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	P.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN -	REVISED -			B69	4RS-4	FRANKLIN	11	4
#MODEL#		CHECKED -	REVISED -		SCALE: SHEET OF SHEETS STA. TO STA.				CONTRACT NO. 78412	
		DATE -	REVISED -						ILLINOIS FED. AID PROJECT	